

AGREEMENT

FOR

CONTRACT PRICE

FOR

PHASE 1A

Dated 20 December 2007

1.0 Introduction

1.1 This document sets out the agreement reached between BBS and tie on 20 December 2007 in respect of the price for the delivery of Phase 1A of the Edinburgh Tram Network.

1.2 Contents

Details of the Agreement

Appendix A1 – Infraco Negotiation Summary Position

Appendix A2 – Detailed Summary Of Contract Price

Appendix A3 – Value Engineering Opportunities Register

Appendix A4 – Provisional Sums

DETAILS OF THE AGREEMENT

2.0 Negotiated Price

- 2.1 The negotiated price for Phase 1a is £218,262,426. Details of the build-up to this price are set out in Appendix A.
- 2.2 The agreed Value Engineering items included in the price are set out in Appendix A3. These sums are fixed reductions save for the conditions listed in Appendix A3 under 'Key Qualifications'.
- 2.3 Provisional sums (previously normalisations) included within the price are as set out in Appendix A4. These allowances are provisional sums for the work described.
- 2.4 All other prices are fixed and firm, based on the Basis of the Price as set out below.

3.0 Basis of the Price

- 3.1 The price is based on the following:
- 3.2 Employers Requirements Version 3.1 as qualified by the BBS Compliance Matrix contained within BBS's Email dated 12 December 2007, save for:-
 - In respect of Prior Approvals and other consents the allocation of risk and responsibility is as set out in the (G Gilbert) email dated 12 December 2007) – Appendix B1
 - OLE – fixed termination system for all on street sections, from Haymarket to Newhaven and within Edinburgh Park and catenary system from Haymarket to Edinburgh Airport. Stepped poles will be adopted throughout.
 - Trackform will be as the RHEDA City system (types C, D and G) except where ballasted track will be adopted as agreed.
 - Maintenance requirements as discussed and as per Email of 12th December and 13th December 2007 – Appendix B2

The Parties acknowledge that the final Employer's Requirements will be subject to quality assurance of the final accepted consolidated version.

- 3.3 The BBS price for civils works includes for any impact on construction cost arising from the normal development and completion of designs based on the design intent for the scheme as represented by the design information drawings issued to BBS up to and including the design information drop on 25th November 2007. The price excludes:-
 - a) Items designated as provisional in the Appendix A4.
 - b) Any material changes to the design resulting from the impact of the kinematic envelope of the CAF tram vehicle on the civils design.
 - c) Excluded items, to the extent described in 3.4 below.In respect of footways, full reuse of existing kerbs and flags and minimal reinstatement behind kerb lines is assumed. i.e. not wall to wall. Design must be delivered by the SDS in line with our construction delivery programme previously submitted.

For the avoidance of doubt normal development and completion of designs means the evolution of design through the stages of preliminary to construction stage and excludes changes of design principle, shape and form and outline specification

3.4 The BBS price for systems works is fixed save for:-

- a) Items designated as provisional in the Appendix A4.
- b) Any agreed material impact of the CAF tram vehicle specification on the traction power supply system as demonstrated by power simulation modelling.

3.5 In all other respects the BBS price is fixed

3.6 Excluded items are:-

- a) Utilities Diversions, except the £3m provisional sum included in the allowance for Picardy Place, York Place and London Road and £0.75m provisional sum for minor utilities diversion as shown in Appendix A4.
- b) Work at St Andrew Square beyond the tram alignment works – tramstops, trackform, track bed, OHLE, road surface refurbishing and associated systems and link works.
- c) The cost of the following within the Forth Ports Area:
 - Road surface finishes, pavings, tramstop finishes and drainage.
 - Work to Tower Place and Victoria Dock bridges.
 - Lindsay Road Retaining Wall and associated highway works.which is extra over the scope included in BBS's price as at selection of BBS as preferred bidder.
- d) The Cost of the Highways and Drainage works at Picardy Place, London Road and York Place that is extra over the scope included in BBS's price as at selection of BBS as preferred bidder.
- e) Ground conditions that require works that could not be reasonably foreseen by an experienced civil engineering contractor based on the ground conditions reports provided to BBS on 20th and 27th of November and 6th December 2007. Additionally the BBS price does not include for dealing with replacement of any materials below the earthworks outline or below ground obstructions/voids, soft material or any contaminated materials.
- f) Bernard Street additional road works as drawing provided.
- g) Completing full footway reconstruction in Leith Walk beyond the allowance made where kerb lines are being re-sited.

3.7 In respect of the Depot excavation works, the price is fixed against the quantities advised to BBS by tie and on the assumption that the depot excavation will be handed over to us pumped dry with a firm sound foundation.

3.8 The price excludes any scope required by Third Parties which is not included within the designs issued up to and including 25th November 2007. BBS and tie will consult with Third Parties prior to contract award to agree local Codes

of Construction Practice. The price will be adjusted for any changes to constraints and additional scope which arises out of these agreements.

3.9 In respect of the highways work in Princes Street, Shandwick Place and Haymarket Junction, BBS's price is based on planing back the existing road structure to a sound base and replacement with an acceptable roads construction suitable for purpose to suit the revised road surface profile. Full depth reconstruction as the current designs in this area is not included in the Price.

3.10 The programme for delivery of Phase 1A is:-

- as represented by the programme provided by BBS dated 11th December 2007 which shows a completion of 8th August 2011 (sent to tie on 13th December 2007 – Appendix B3),
- based on the contents and assumptions set out in BBS email (Steve Sharpe) dated 13th December 2007 – Appendix B4, BBS and tie will work to deliver completion of Phase 1a by 11th Feb 2011 and
- based on the constraints and methodologies as agreed between BBS, tie, TEL and CEC.

It is agreed that all parties must work together to achieve the rationalisation of city centre constraints to achieve programme delivery. BBS have not allowed in the Price for completion beyond March 2011.

3.11 Contract terms as represented by the negotiations up to 14th Dec 2007 and for the avoidance of doubt:-

- a) Consents as set out in tie email (Geoff Gilbert) to BBS dated 12th December 2007 – Appendix B1.
- b) Third Party Agreement and Third Party obligations as set out in BBS email (M Flynn) dated 12th December 2007 – Appendix B5.
- c) The novation of SDS to Infracore as set out in the Novation Plan.
- d) The novation of Tramco to Infracore at the date of Infracore Contract Award.
- e) The terms negotiated and under negotiation prevail over statement in respect of contract issues stated in the technical information submitted by BBS.

3.12 In all other respects the conditions of the Preferred Bidder Agreement apply.

4.0 Agreement

4.1 This document is agreed as a record of the outcome of the negotiations:-

for and on behalf of tie LIMITED

on the 20th December 2007

Authorised signatory:

Full name: WILLIAM CALLAGHER

EXECUTED for and on behalf of BBS

on theDecember 2007

Authorised signatory: [REDACTED]

Full name: *R G WALKER* *BILANZ & BERGER*

Authorised Signatory

[REDACTED]

21/12/07

Full Name: *S. WERBOW*

SIEMENS

APPENDIX A

APPENDIX B1

APPENDIX B2

APPENDIX B3

APPENDIX B4

APPENDIX B5

INFRACO NEGOTIATION SUMMARY POSITION

Date:- 18/12/07

	Current £m	Comments
Fixed Elements		See Appendix A2 for further details
Core contract sum - firm price	211,910,342	
Provisional elements taken into firm	0	All previously provisional items taken to firm
VE taken into firm price	-83,000	
VE taken into firm price - but conditional	-11,065,006	See conditions referred to in Appendix A3
Premium for current provisional items	8,000,000	Negotiated sum for firming up all elements
Total firm price	208,762,336	94%
Provisional Sums	12,170,090	Previous normalisations which are still relevant - See Appendix A4 plus £2m provisional sum for SDS design post novation (See RW Email 11/10/07)
Total Provisional	12,170,090	
Sub total	220,932,426	
Remaining Identified VE	-2,670,000	To be stated in contract with rules for adjustment of price and commitments for both parties work to deliver these items
Anticipated Infraco Contract Sum (Final Deal)	218,262,426	

DETAILED SUMMARY OF CONTRACT PRICE

APPENDIX A2

Item	Prelims	Trackform - System	Depot	Structures - Superstructure	Highways	Tramstops	Buildings	Supervisory & Comms	DLE	Tramstop Equipment	Trams	Reduction as BBS letter 11/10/07	Reduction for taking CAF into BBS Consortia	Traction Power	Power for commissioning	System Wide	Network Rail	Total
Base																		
Firm	73,437,757	43,918,161	18,666,351	31,415,121	11,893,955	3,270,376	3,275,180	5,296,482	14,974,462	1,513,587	1,018,910	-1,000,000			1,330,000	-120,000	3,000,000	211,910,342
Provisional	2,000,000																	2,000,000
Firm price addition																8,000,000		8,000,000
Sub-total Base	75,437,757	43,918,161	18,666,351	31,415,121	11,893,955	3,270,376	3,275,180	5,296,482	14,974,462	1,513,587	1,018,910	-1,000,000	0	0	1,330,000	7,880,000	3,000,000	221,910,342
Provisional (See Appendix A4 for details)																		
Provision of pumped surface water outfall system at A8 underpass			100,000															100,000
Spares not included in Price									174,762									174,762
Scottish Power Connections to Depot and IPR									760,000									760,000
Relocation of Ancient Monuments	53,700																	53,700
Allowance for minor utility diversions		750,000																750,000
Archaeological Officer - impact on productivity		405,755																405,755
Ballast		300,000																300,000
Picardy Place, York Place and London Road junction					6,340,324													6,340,324
E/O Shell Grip					315,343													315,343
Mains Power Connection to street lights and traffic signals					115,287													115,287
Adjust for Network Rail Possessions support				755,307														755,307
Leith Walk substation demolition				55,662														55,662
Additional Crew Relief Facilities at Haymarket				49,950														49,950
Sub-total - Provisional Normalisation	53,700	1,455,755	100,000	860,919	6,774,955	0	0	0	924,762	0	0	0	0	0	0	0	0	10,170,090
Value Engineering																		
Firm																		
NR Immunisation. NOW IN FIRM PRICE - SEE ABOVE																		0
Signalling & Comms - fewer CCTV cameras																		-33,000
Reduced to 55Nr. (Tramstops 45Nr, Depot 10Nr)																		-50,000
UPS - reduce capacity from 4hrs to 3hrs																		0
Sub-total - Firm Value Engineering	0	0	0	0	0	0	0	-83,000	0	0	0	0	0	0	0	0	0	-83,000
Firm with conditions																		
Delete depot pumping station/storm tanks by utilising existing gravity system.			-193,526															-193,526
Depot - Build part now with provision to expand in the future/reduce size of car park facilities			-230,000															-230,000
Delete under floor lift plant and utilise mobile jacks. incl mobile future proofing.			-250,000															-250,000
Depot - delete split vehicle accommodation system - requirement dependant on tram vehicle selection			-27,500															-27,500
Depot - Track Maintenance Equipment - rationalise scope requirement and consider renting.			-27,500															-27,500
Depot - deletion of one pavement (inner)			-36,000															-36,000
Depot - delete requirement for concrete apron to security fence			-6,080															-6,080
Depot - delete compressed air system, utilise 1 or 2 local/mobile compressors			-54,400															-54,400
Consolidated VE items 7, 10, 11, 19 which results from changes to initial Depot design driven by proximity to BAA runway and EARL decision.			-2,200,000															-2,200,000
Delete standby generator and substitute with hardstanding and power connection for portable generator.			-150,000															-150,000
Material recovery and reprocessing (Infracore); 2 options - reconstituted planings & Type 1R					-500,000													-500,000
Reduce Kerb and associated re-instatement of pavement					-100,000													-100,000
Reduce drainage run from guideway					-100,000													-100,000
Overhead Contact system - Switchgear - rationalise specification - considered "quite onerous"									-160,000									-160,000
Edinburgh Park Bridge - 7 span to 2, utilise steel beams in lieu of concrete Edinburgh Park Viaduct				-1,470,000														-1,470,000
Camicknowe Bridge Parapet - down grade from P8 / P5 to N2 (reduced cost of parapet plus knock on effect on deck design/cost)				-85,000														-85,000
A8 Underpass various initiatives				-850,000														-850,000
Roseburn Street Viaduct various initiatives				-1,375,000														-1,375,000

CEC02085660_0025

17/01/2008

DETAILED SUMMARY OF CONTRACT PRICE

APPENDIX A2

Item	Prelims	Trackform - System	Depot	Structures - Superstructure	Highways	Tramstops	Buildings	Supervisory & Comms	OLE	Tramstop Equipment	Trams	Reduction as BBS letter 11/10/07	Reduction for taking CAF into BBS Consortia	Traction Power	Power for commissioning	System Wide	Network Rail	Total
Water of Leith various initiatives				-150,000														-150,000
Eight maintenance walkway structures - delete or reduce				-250,000														-250,000
Class 7 material conversion -																		
Optimise the work site lengths wherever practical to ensure efficient construction outputs				-300,000														-300,000
Accept more disruption over shorter period to maximise efficiency of construction operations -																		-300,000
Option to lease UPS provision from Supplier rather than purchase																		-100,000
Rationalising spares supplied with the Infraco bid																		-300,000
PM Integration including shared resources and co-location.																		-300,000
Noise attenuation (outside of Roseburn Corridor) 3,650m of fencing		-50,000																-1,000,000
Reduce ballasted track thickness from 300 to 200mm		-200,000																-50,000
Power Supply (up to passenger operation) - possible over allowance in DFBC														-300,000				-200,000
Sub-total - Provisional Value Engineering	0	-250,000	-3,175,006	-4,480,000	-700,000	0	0	0	-160,000	0	0	0	0	-300,000	0	-2,000,000	0	-11,065,006
Further project management integration over 3 years																		-500,000
SDS design scope economy, variation and reduction																		-500,000
Tramstops, standard finishes to circa 20-30% of stops										-500,000								-500,000
Picardy place level flexing - MUDFA savings					-500,000													-500,000
Picardy place level flexing - construction savings					-500,000													-500,000
Siemens agreement to reduce fixed price on item 49 above by £10,000. Now included in item 49 above.																		0
Siemens agreement to reduce fixed price on item 145 above by £200,000. Now included in item 145 above.																		0
Value engineer finishes on EPV and other structures				-170,000														-170,000
Other unidentified VE items																		0
Sub-total - Provisional Value Engineering	0	0	0	-170,000	-1,000,000	0	0	0	0	-500,000	0	0	0	0	0	-1,000,000	0	-2,670,000
Total Anticipated Value	75,491,457	45,373,916	18,786,351	32,106,040	17,668,910	3,270,376	3,275,180	5,213,482	15,899,224	1,013,587	1,018,910	-1,000,000	0	0	1,330,000	6,880,000	3,000,000	218,262,426

VALUE ENGINEERING OPPORTUNITIES REGISTER

REF	ITEM	FILTER	VALUE		NOTES	Key Qualifications
			Target	Agreed BBS position		
	BUILDINGS					
					The 2 sub-station items have been rejected by BBS.	
	BUILDINGS TOTAL		£0	£0		
	DEPOT					
8	Delete depot pumping station/storm tanks by utilising existing gravity system.	Depot	£193,526	£193,526	tie may need to add in cost of a small pump	tie's carries specification/acceptance risk and cost of additional pump
9	Depot - Build part now with provision to expand in the future/reduce size of car park facilities	Depot	£230,000	£230,000	Initial supply of 100 car park places agreed.	tie's carries specification/acceptance risk
14	Delete under floor lift plant and utilise mobile jacks. Incl mobile future proofing.	Depot	£250,000	£250,000		tie's carries specification/acceptance risk
16	Depot - delet split vehicle accommodation system - requirement dependant on tram vehicle selection	Depot	£27,500	£27,500	Accommodation bogies are in CAF offer	tie's carries specification/acceptance risk
17	Depot - Track Maintenance Equipment - rationalise scope requirement and consider renting.	Depot	£27,500	£27,500		tie's carries specification/acceptance risk
20	Depot - deletion of one pavement (inner) .	Depot	£36,000	£36,000	Shown on latest site plan drawings.	tie's carries specification/acceptance risk
24	Depot - delete requirement for concrete apron to security fence	Depot	£6,080	£6,080		tie's carries specification/acceptance risk
129	Depot - delete compressed air system, utilise 1 or 2 local /mobile compressors	Depot	£54,400	£54,400		tie's carries specification/acceptance risk
145	Consolidated VE items 7, 10, 11, 19 which results from changes to initial Depot design driven by proximity to BAA runway and EARL decision.	Depot	£3,181,264	2,000,000	Includes rreductions in structural loadings (gantry crane reduced in capacity and size impacting on building frame and envelope), reductions in staff accommodation provision (reduced operational workforce reducing messing facilities, changing rooms, locke	DTC but compliant with current technical /design info. Subsequent saving of £200,000 added see below.
New	Delete standby generator and substitute with hardstanding and power connection for portable generator.	Depot	£250,000	150,000		tie's carries specification/acceptance risk

VALUE ENGINEERING OPPORTUNITIES REGISTER

REF	ITEM	FILTER	VALUE		NOTES	Key Qualifications
	DEPOT TOTAL		£4,256,270	£2,975,006		
	HIGHWAYS					
36b	Material recovery and reprocessing (Infracore); 2 options - reconstituted planings & Type 1R	Highways	£500,000	£500,000		Subject to confirmation from SDS; level of saving subject to adjustment of quantity of this item based on the final design
152	Reduce Kerb and associated re-instatement of pavement	Highways	£100,000	£100,000		Subject to confirmation from SDS; level of saving subject to adjustment of quantity of this item based on the final design
153	Reduce drainage run from guideway	Highways	£100,000	£100,000		Subject to confirmation from SDS; level of saving subject to adjustment of quantity of this item based on the final design
	HIGHWAYS TOTAL		£700,000	£700,000		
	NETWORK RAIL					
42	NR Immunisation - ensure design of immunisation is based on minimum safe propagation distance (e.g. <100m). Project budget previously very conservative.	NR	£4,700,000	4,700,000	Original proposal work by BBS suggests a target of less <50m may be achievable.	Terms remain as BBS letter; particularly that tie carries NR cost risk
	NETWORK RAIL TOTAL		£4,700,000	£4,700,000		
	OLE					
49	Overhead Contact system - Switchgear - rationalise specification - considered "quite onerous"	OLE	£336,000	150,000	Price change requested for manual, three position cubicle mounted line isolators throughout, with the exception of the depot where they can be pole mounted. Status of isolator to be shown via SCADA.	Siemens commitment related to non specific items
135	OLE - Catenary opportunity in Sections 5 to 7 - replace trolley wire with catenary on segregated sections.	OLE		0	Detailed price change requested for: catenary with 3-step poles Haymarket Yard-Russell Road (Russell Road-Airport already catenary); fixed termination Haymarket Yards-Newhaven; Tapered Poles Haymarket-Newhaven.	No net savings. All in price. Assumes fully compliant with planning and technical requirements but excludes tapered poles.
149	Provision of combined incoming and return cabinet.	OLE	£42,000	0		tie proven to be incompatible with SP feeder arrangements.
	OLE TOTAL		£378,000	£150,000		
	STRUCTURES					
54	Value Engineering/ de-risked pricing approach developed for the final designs for all structures, particularly substructures and foundations (where not covered below)	Structures	£2,000,000	0		Unable to commit
55	Edinburgh Park Viaduct various savings including use of cross heads to eliminate temp works, steel or concrete beams.	Structures	£1,470,000	1,470,000	This assumes continuation with 7 span structure.	Subject to approval of design by NEL/ CEC and subject to SDS designing to cost

VALUE ENGINEERING OPPORTUNITIES REGISTER

REF	ITEM	FILTER	VALUE		NOTES	Key Qualifications
56	Carricknowe Bridge Parapet - down grade from P6 / P5 to N2 (reduced cost of parapet plus knock on effect on deck design/cost)	Structures	£85,000	85,000		Subject to approval of design by Network Rail
57	A8 Underpass various initiatives	Structures	£850,000	850,000	Changing to a contiguous piled wall/ leaner designs	Subject to being able to design to cost
New	Roseburn Street viaduct various initiatives	Structures	£1,375,000	£1,375,000		Subject to approval by stakeholders - SRU and Network Rail
New	Water of Leith various initiatives	Structures	£150,000	150,000		Subject to being able to design to cost
New	Eight maintenance walkway structures - delete or reduce	Structures	£250,000	250,000	Unlikely to yield net savings unless structure needs to be redesigned for other purposes.	Subject to being able to design to cost; and tie taking approvals risk
New	Russel rd Bridge piling changes	Structures	£100,000	0		Subject to being able to design to cost
154.	Class 7 material conversion -	Structures	£300,000	£300,000		Subject to confirmation of SDS agreeing to principle; level of saving subject to adjustment of quantity of fill required by the final design
STRUCTURES TOTAL			£6,580,000	£4,480,000		
SUPERVISORY & COMMS						
65	Signalling & Comms - fewer CCTV cameras . Reduced to 55Nr . (Tramstops 45Nr, Depot 10Nr)	Supervisory & Comms	£100,000	33,000	Price requested for 55 off for Phase 1a	
69	Signalling & Comms - rationalise fibre optic ring. More economic architecture that performs the same function could be employed	Supervisory & Comms	£100,000	0	Ensure separation 1a and 1b costs	
73	Signalling & Comms - Current requirement for location and interface of the SCADA and Points controllers etc is unnecessarily complex.	Supervisory & Comms	£50,000	0	A simpler solution e.g. as in Nottingham, would be cheaper and more user friendly.	
74	Signalling & Comms - rationalise loop quantities by combining some loop functions	Supervisory & Comms	£87,500	0		
75	Signalling & Comms - Remove ambient noise sensing on the passenger announcement system	Supervisory & Comms	£7,000	0	Price change requested.	
163	UPS - reduce capacity from 4hrs to 3hrs	Supervisory & Comms	£50,000	50,000	Would be included in financial advantage for proposal to outsource UPS provision to Chloride.	
165	Reduce nr of Signalised Pedestrian Xings.	Supervisory & Comms	?	0	From review of latest road layouts there is a significant increase in qtys. May need to challenge CEC (c.£50k/ crossing)	
SUPERVISORY & COMMS TOTAL			£394,500	£83,000	BBS have agreed to review Phase 1a/1b split. Still outstanding.	
SYSTEM WIDE						
77	Optimise the work site lengths wherever practical to ensure efficient construction outputs	System Wide	£300,000	300,000	Linked to other discussions e.g. Rhaeda City trackform (see 138 too)	Subject to further Programme development with CEC, confirm by 9th January.
80	Accept more disruption over shorter period to maximise efficiency of construction operations -	System Wide	£100,000	100,000	Initial discussions suggests CEC are likely to be flexible	Subject to further Programme development with CEC, confirm by 9th January.

CEC02085660_0033

71214 Single VE List v31 agreed bbs tie v1

VALUE ENGINEERING OPPORTUNITIES REGISTER

REF	ITEM	FILTER	VALUE		NOTES	Key Qualifications
148	Remove spare capacity from OTN (linked to item 69)	System Wide	£180,000	0		
150	Option to lease UPS provision from Supplier rather than purchase	System Wide	£300,000	300,000	Originally BBS proposal	Subject to agreement of operator
151	Rationalising spares supplied with the Infraco bid	System Wide	£300,000	300,000	Originally BBS proposal	Subject to agreement of operator
160	PM Integration including shared resources and co-location.	System wide	£1,000,000	1,000,000	Late BBS VE proposal	Subject to BBS /tie agreeing savings in resources and facilitates items from BBS and tie costs
SYSTEM WIDE TOTAL			£2,180,000	£2,000,000		
TRACK FORM						
100	Noise attenuation (outside of Roseburn Corridor) 3,650m of fencing	Trackform	£50,000	50,000	Also a timing issue, because we would not necessarily install during construction but await reaction if any.	Subject to property owner claims
138	Trackform - changing embedded to ballast rail. Ballasted track adjacent to NwkRail	Trackform	£2,000,000	0	Awaiting a formal technical and financial proposal for Rhaeda City trackform for both embedded and grass and a validated construction programme.	Unlikely to yield savings because of short distance. Plus maintenance implications.
156	Track installation install in strips.	Trackform	£0	0	Would need v strong justification.	Unacceptable
164	Reduce ballasted track thickness from 300 to 200mm	Trackform	£300,000	200,000		Design to cost.
TRACK FORM TOTAL			£2,350,000	£250,000		
TRACTION POWER						
103	11Kv Traction Power feeds to sub stations including any network reinforcement required (separate VE 104).	Traction Power	?	0	Dialogue needed with tie to incorporate SP negotiated savings into BBS proposal.	Defer until SP current phase of negotiations is complete.
109	Power supply - Russell Rd TPH - equipment for future upgrade to substation to be supplied when needed i.e. don't supply transformer rectifier now.	Traction Power	?	0	BBS have been instructed to assume that for Ph 1a on its own nothing at all will be required at Russell Road. Separate discussion re Phase 1b still continuing.	BBS to check equipment included and advise. ASAP
158	Power Supply (up to passenger operation) - possible over allowance in DFBC	Traction Power	£300,000	300,000		Subject to tie demonstrating evidence.
TRACTION POWER TOTAL			£300,000	£300,000		
New	Other unidentified VE items	Other	£1,000,000	£0		Need specifics for BBS commitment therefore zero.
UNIDENTIFIED VE TOTAL			£1,000,000	£0		
				£0		Need specifics for BBS commitment therefore zero.
NEW INITIATIVES AGREED AFTER MAIN MEETING						

VALUE ENGINEERING OPPORTUNITIES REGISTER

REF	ITEM	FILTER	VALUE	NOTES	Key Qualifications
New	Further project management integration over 3 years		£500,000		Joint target
New	SDS design scope economy, variation and reduction		£500,000		Joint target
New	Tramstops, standard finishes to circa 20-30% of stops		£500,000		Joint target
New	Picardy place level flexing - MUDFA savings		£500,000		tie led initiative
New	Picardy place level flexing - construction savings		£500,000		Joint target
NOTE	BB agreement to reduce fixed price £120,000		£120,000	for the record only (not part of VE savings)	BB risk
NOTE	Siemens agreement to reduce fixed price on item 49 above by £10,000		£10,000		Siemens risk
NOTE	Siemens agreement to reduce fixed price on item 145 above by £200,000		£200,000		Siemens risk
New	Value engineer finishes on EPV and other structures	Structures	£170,000		Subject to approval by NEL/CEC
	NEW VE INITIATIVES TOTAL		£0	£3,000,000	
	TOTAL			18,638,006	

PROVISIONAL SUMS

APPENDIX A4

Description	BBS 3		Total
	1A	1B	
34 . Provision of pumped surface water outfall system at A8 underpass	100	-	100
62 . Spares not included in Price	175	100	275
70 . Scottish Power Connections to Depot and IPR	750	-	750
71 . Relocation of Ancient Monuments	54	-	54
63 . CCTV cameras		313	313
8 . E/O carrier drains	-	1,645	1,645
16 . Allowance for minor utility diversions	750	250	1,000
23 . Archaeological Officer - impact on productivity	406	-	406
64 . Ballast	300	-	300
50 . Gogarburn Tram Stop By RBS		-	-
Sub Total Infraco Normalisation exc. Highways & Struct	2,534	2,307	4,842
3 . Piccardy Place, York Place and London Road junction	6,340	-	6,340
4 . Extent of road refinishing in critical on street areas		-	-
22 . E/O Shell Grip	319	126	445
27 . Mains Power Connection to street lights and traffic signals	115	29	144
Sub Total Highways	6,775	154	6,929
19 . Adjust for Network Rail Possessions support	755	-	755
20 . Balgreen Road - new structure reqd		-	-
26 . S23 Carrick Knowe Widening		-	-
28 . Leith Walk substation demolition	56	-	56
31 . Additional Crew Relief Facilities at Haymarket	50	-	50
32 . Structure S18 allowance for anticipated works		-	-
61 . Roseburn corridor retaining wall align assumptions	-	3,228	3,228
Sub Total Structures	861	3,228	4,089
Total	10,170	5,690	15,860

CEC02085660_0039

APPENDIX A

APPENDIX B1

Geoff Gilbert

From: Geoff Gilbert
Sent: 12 December 2007 21:00
To: flynn.michael@siemens.com
Cc: Tom.Murray@bilfinger.co.uk; 'Scott.McFadzen@bilfinger.co.uk';
Richard.Walker@bilfinger.co.uk; Bob Dawson; Valerie Clementson
Subject: Draft Consents Paper GG 121207
Attachments: Draft Consents Paper GG 121207.doc

Michael

Simplified proposal from us on consents enclosed. Can we discuss tomorrow morning.

Regards

Geoff Gilbert - Project Commercial Director

TRAM Project

tie Limited

Citypoint

65 Haymarket Terrace

Edinburgh EH12 5HD

tel [REDACTED]

mob [REDACTED]

20/12/2007

CEC02085660_0045

**Edinburgh TRAM Project
(Commercial In Confidence)**

Subject : Infraco Contract Terms Clarifications
Review area : Consents
Date : 12th December 2007

1.0 Principles

2.1 The allocation of responsibility for consents in the contract will be as follows:-

- The following consents will be the responsibility of tie to obtain
 - TROs for the permanent scheme
 - TTROs to enable the scheme to be constructed, with BBS support (tie have already applied for blanket TTRO's)
 - Network Rail possessions – tie book these based on BBS programme dates (note these are already booked now wrong dates – need to be re-booked to comply with revised Infraco Contract)
- BBS provides relevant support to tie to obtain these consents.
- SDS obtain other consents required to fulfil their contract obligations. Agreed consents being obtained by SDS will be clarified in the novation agreement with a list of consents stating the status of consents at Novation. The list of consents being obtained by SDS is set out in Appendix A.
- BBS obtain all other consents, those required for construction activities and also those required to commission the system and enable it to open for passenger carrying operation. Support is provided by SDS where relevant.
- Tie will provide support to BBS to assist them in obtaining consents from third parties where they are not co-operating, provided BBS has provided the requisite information to obtain the consent and comply with the consent authorities timescales.
- Where consents are not put in place by SDS to meet the BBS programme in the Infraco Proposals then the impact on programme will be a CE, subject to certain provisos as set out later in this paper.

Tie will consider a CE where BBS are unable to obtain consents. To enable tie to assess whether it is prepared to do this SDS is to advise tie of the specific consents that it is concerned about. Tie will not agree to a blanket CE for all consents to be obtained by Infraco. Where tie agrees to a CE where BBS are unable to obtain consents this will be subject to the provisos listed below in 9 below.

2.0 Traffic Regulation Orders [TROs]

- 2.1** The TROs are to be obtained by tie with relevant technical support and programme information being provided by BBS.
- 2.2** If BBS action or inaction delays this process and to the extent that this delays completion of the scheme will not be a CE.

3.0 Temporary Traffic Regulation Orders [TTROs]

**Edinburgh TRAM Project
(Commercial In Confidence)**

- 3.1 The TTROs are to be obtained by tie but based on the programme and technical information being provided by BBS, including traffic management proposals. This will in essence be the implementation of the On Street Construction Works Methodology which is to contain all the details necessary for tie to draw down a TTRO, including traffic management arrangements proposed by BBS.
- 3.2 If BBS action or inaction delays this process and to the extent that this delays completion of the scheme will not be a CE.
- 4.0 Network Rail**
- 4.1 Possessions have already been booked by tie in accordance with BBS's requirements. Possessions need to be re-booked to suit revised Infraco Contract.
- 4.2 BBS (including providing design and technical information where necessary) will prepare and provide to tie all necessary paperwork to enable tie to make an application for possessions to Network Rail.
- 4.3 The responsibility for payment for these possessions will rest with tie but any changes to possessions as a result of BBS being in culpable delay will then rest with BBS.
- 4.4 Any changes to possessions as a result of Network Rail will, subject to usual tests, lead to a Compensation Event for BBS.
- 5.0 Discharge Consents (water)**
- 5.1 There are two situations here, namely:
- Temporary Discharge Consents
 - Permanent Discharge Consents
- 5.2 Clearly BBS has to be responsible for temporary discharge consents as these will relate to their method of working or other preliminaries items such as their site set up.
- 5.3 With regard to the permanent discharge consents BBS want these to be in place prior to novation of SDS. If this can be achieved then it would be the preferred position. BBS to check SDS programme to determine whether these are in place.
- 5.4 It is logical that BBS are responsible for obtaining the permanent discharge consents as SDS will be their consultant not tie's for this element of the work. Permanent discharge consents are required prior to commencement of the relevant drainage works. If these are refused due to SDS errors it will be a matter for BBS to resolve with SDS (subject to the SDS having obtained a permanent discharge consent and designed an agreed outfall arrangement for the Depot?). However if refused or made conditional upon works being

**Edinburgh TRAM Project
(Commercial In Confidence)**

undertaken e.g. betterment, upgrading, new or renewal requirements for other reasons outside of BBS/SDS control then it is suggested that this becomes a tie change.

6.0 Building Warrants

6.1 The Building Warrants relate to compliance with technical standards and thus it is appropriate that this rests with BBS (SDS providing this to BBS other than where BBS have or are to undertake the design).

7.0 Building Fixing Agreements (for overhead line)

7.1 SDS have a responsibility to obtain Building Fixing Agreement and thus under the novation arrangement this will rest with BBS.

7.2 However tie has already acknowledged that obtaining a Building Fixing Agreement is not necessarily guaranteed. Heritable Proprietors (owners) have the right to object and quite probably most will. Thereafter CEC/tie determines whether to take the matter to the Sheriff Court.

7.3 Although Building Fixings Agreements remain as the preferred solution, SDS is also progressing the approval of poles to support the overhead line.

7.4 If Building Fixing Agreement is not obtained in a particular location, then within limits of being technically feasible and programme constraints for a new request, alternative locations for a Building Fixing are to be sought.

7.5 Where it is not technically feasible to use an alternative location for a Building Fixing or the programme constraints are insufficient for a new request, then the 'fall-back position' of the use of a pole becomes a tie Change.

7.6 Where there is uncertainty of likely outcome, consideration will be given to a dual approach of seeking Building Fixings and also installing foundations for a pole (as a tie Change).

8.0 Other consents related to design

10.1 All other consents related to design will rest with BBS.

9.0 Compensation Event where consents are not obtained or are delayed by SDS

11.1 BBS will be entitled to a CE where a consent is not provided by the authority providing the consent by the date that it is shown as required on the programme included in the Infracore Proposals provided that:

- It relates to a consent that SDS are due to obtain in accordance with their contract (excluding any additional consents that Infracore may have instructed SDS to obtain after novation)
- Infracore explains the reasons given by the consenting authority as to why they will not or have not provided consent within the agreed period (with supporting documentation)

**Edinburgh TRAM Project
(Commercial In Confidence)**

- Infraco advises tie immediately that it becomes aware that a consent may not be obtained by the due date. In such circumstances Infraco will afford tie the opportunity to meet with the authority providing the consent with a view to resolving the situation and Infraco attends the meeting with tie and supports tie in this respect.
- Infraco demonstrates that:-
 - Not receiving the consent has had or will have a material impact on the progress of the works
 - Infraco have taken all reasonable steps to obtain the consent
 - Infraco has provided all information necessary to obtain the consent within the timescales agreed with the authority providing the consent
 - the failure by the authority required to provide the consent has not been brought about by Infraco reprogramming the works or reprogramming or reprioritising the design programme such that a timescale agreed with the authority providing the consent cannot now be achieved
 - the authority providing the consent has not responded within the agreed timescales
 - Infraco has undertaken or plans to undertake mitigation actions in a timely manner to avoid or mitigate the impact of any delay in obtaining consent.
 - The failure in obtaining a consent is not due to a failure on the part of SDS to deliver the obligations of their contract.

**CONSENTS
(Commercial In Confidence)**

Railways and Aviation	HMRI	HMRI	Ongoing process with HMRI
	Network Rail	Network Rail	Ongoing negotiations with NR
	BAA/Aviation Consents	BAACAA/NATS	Ongoing negotiations with BAA
Planning	Listed Building Consent	CEC Planning Authority	
	Prior Approval	CEC Planning Authority	
	Planning Permission	CEC Planning Authority	
	Conservation Area Consent	CEC Planning Authority	Not applicable within LoD
	Scheduled Monument Consent	Scottish Executive & Historic Scotland	
	Advertisement Consent	CEC Planning Authority	Information signs "deemed consent"
Traffic Management	Road Construction Consent	CEC Roads Authority	
Environment Ecological	Badger Licence	Scottish Natural Heritage	Environmental Team
	Otter holt/disturbance licence	Scottish Natural Heritage	
	Bat Licence	Scottish Natural Heritage	
	Appropriate Assessment	Competent Authority	
Drainage CAR	CAR General Binding Rules	SEPA	
	CAR Registration	SEPA	
	CAR License	SEPA	
	Water/ Wastewater Connection	Scottish Water	
Construction	Technical Approval	CEC Bridges/ CEC Roads	
	Building Warrant	CEC Building Standards	
Radio	OFCOM license	OFCOM	
Design Consultation	Third Party Design Consultation		
Undertakings	Undertakings to Parliament	n/a	Undertakings and Agreements to Parliament and with 3rd parties that must be met
Agreements	Agreements with 3rd Parties	n/a	
Letter of Comfort	Letter of comfort	n/a	
Letter of Closure	Letter of Closure	n/a	

APPENDIX B2

Geoff Gilbert

From: Alastair Richards - TEL
Sent: 20 December 2007 18:27
To: Geoff Gilbert
Subject: FW: Employer's Requirements - 3.03 (draft) - Maintenance Section
Attachments: ERs - Maintenance - Draft 3 03 for Informal Issue ONLY_rev20071211.pdf

From: Brauns, Bernhard [mailto:bernhard.brauns@siemens.com]
Sent: Wed 12/12/2007 7:23 PM
To: Alastair Richards - TEL
Cc: scott.mcfadzen@bilfinger.de; Brueckmann, Roland
Subject: AW: Employer's Requirements - 3.03 (draft) - Maintenance Section

Hello Alastair,

please find attached the ER with my comments (directly in the pdf document).

In case you can't see the comments, please give me a ring - I'd then have to convert the pdf into a Word document.

With best regards,
Bernhard Brauns

Siemens AG
Transportation Systems
Integrated Services
TS IS S12
Sieboldstr. 16
91052 Erlangen, Germany
Tel.: +49 [REDACTED]
Fax: +49 [REDACTED]
Mobile: + [REDACTED]
mailto:bernhard.brauns@siemens.com

Siemens Aktiengesellschaft: Chairman of the Supervisory Board: Gerhard Cromme; Managing Board: Peter Loescher, Chairman, President and Chief Executive Officer; Heinrich Hiesinger, Joe Kaeser, Rudi Lamprecht, Eduardo Montes, Juergen Radomski, Erich R. Reinhardt, Hermann Requardt, Uriel J. Sharef, Peter Y. Solmssen, Klaus Wucherer; Registered offices: Berlin and Munich; Commercial registries: Berlin Charlottenburg, HRB 12300, Munich, HRB 6684; WEEE-Reg.-No. DE 23691322

Von: Alastair Richards - TEL [mailto:Alastair.Richards@tie.ltd.uk]
Gesendet: Freitag, 7. Dezember 2007 18:52
An: Brauns, Bernhard
Betreff: FW: Employer's Requirements - 3.03 (draft) - Maintenance Section
Wichtigkeit: Hoch

Bernhard,

following our meeting, I have updated the Maintenance section and attached it for your informal review. We are finalising the reissue of the consolidated ER's early next week and any feedback would be helpful.

Regards,

20/12/2007

CEC02085660_0059

Alastair

From: Glen Aitken
Sent: Fri 12/7/2007 4:51 PM
To: Alastair Richards - TEL
Subject: Employer's Requirements - 3.03 (draft) - Maintenance Section

Alastair,

As requested, Please find attached the prospective (draft) 3.03 version of the Maintenance Section of the Employer's Requirements.

Have a great weekend.
With kind regards,

Glen

Glen Aitken
Engineering Project Administrator

tie limited
Citypoint
65 Haymarket Terrace
Edinburgh EH12 5HD

tel. +44 (0) XXXXXXXXXX

email. Glen.Aitken@tie.ltd.uk
web. www.tie.ltd.uk

The information transmitted is intended only for the person to whom it is addressed and may contain confidential and/or privileged material. If you are not the intended recipient of this e-mail please notify the sender immediately at the email address above, and then delete it.

E-mails sent to and by our staff are monitored for operational and lawful business purposes including assessing compliance with our company rules and system performance. TIE reserves the right to monitor emails sent to or from addresses under its control.

No liability is accepted for any harm that may be caused to your systems or data by this e-mail. It is the recipient's responsibility to scan this e-mail and any attachments for computer viruses.

Senders and recipients of e-mail should be aware that under Scottish Freedom of Information legislation and the Data Protection legislation these contents may have to be disclosed to third parties in response to a request.

tie Limited registered in Scotland No. SC230949. Registered office - City Chambers, High Street, Edinburgh, EH1 1YT.

20/12/2007

CEC02085660_0061

Geoff Gilbert

From: Alastair Richards - TEL
Sent: 20 December 2007 18:23
To: Geoff Gilbert
Subject: FW: Employer's Requirements - 3.03 (draft) - Maintenance Section

As requested

From: Alastair Richards - TEL
Sent: Wed 12/12/2007 7:52 PM
To: Brauns, Bernhard
Cc: scott.mcfadzen@bilfinger.de; Brueckmann, Roland
Subject: RE: Employer's Requirements - 3.03 (draft) - Maintenance Section

Berhard,

thanks for this, I can see the comments, they seem to be mainly clustered in Table 92 Fault Corrective Requirements. Probably best if we discuss these specifically on the telephone tomorrow one by one to find a resolution. How would 10:30 your time suit you?

Regards,

Alastair

From: Brauns, Bernhard [mailto:bernhard.brauns@siemens.com]
Sent: Wed 12/12/2007 7:23 PM
To: Alastair Richards - TEL
Cc: scott.mcfadzen@bilfinger.de; Brueckmann, Roland
Subject: AW: Employer's Requirements - 3.03 (draft) - Maintenance Section

Hello Alastair,

please find attached the ER with my comments (directly in the pdf document).

In case you can't see the comments, please give me a ring - I'd then have to convert the pdf into a Word document.

With best regards,
Bernhard Brauns

Siemens AG
Transportation Systems
Integrated Services
TS IS S12
Sieboldstr. 16
91052 Erlangen, Germany
Tel.: +49 [REDACTED]
Fax: +49 [REDACTED]
Mobile: + [REDACTED]
<mailto:bernhard.brauns@siemens.com>

Siemens Aktiengesellschaft; Chairman of the Supervisory Board: Gerhard Cromme; Managing Board: Peter Loescher, Chairman, President and Chief Executive Officer; Heinrich Hiesinger, Joe Kaeser, Rudi Lamprecht, Eduardo Montes, Juergen Radomski, Erich R. Reinhardt, Hermann Requardt, Uriel J. Sharef, Peter Y. Solmssen, Klaus Wucherer; Registered offices: Berlin and Munich; Commercial registries: Berlin Charlottenburg, HRB 12300, Munich, HRB 6684; WEEE-Reg.-No. DE 23691322

20/12/2007

CEC02085660_0063

Von: Alastair Richards - TEL [mailto:Alastair.Richards@tie.ltd.uk]
Gesendet: Freitag, 7. Dezember 2007 18:52
An: Brauns, Bernhard
Betreff: FW: Employer's Requirements - 3.03 (draft) - Maintenance Section
Wichtigkeit: Hoch

Bernhard,

following our meeting, I have updated the Maintenance section and attached it for your informal review. We are finalising the reissue of the consolidated ER's early next week and any feedback would be helpful.

Regards,

Alastair

From: Glen Aitken
Sent: Fri 12/7/2007 4:51 PM
To: Alastair Richards - TEL
Subject: Employer's Requirements - 3.03 (draft) - Maintenance Section

Alastair,

As requested, Please find attached the prospective (draft) 3.03 version of the Maintenance Section of the Employer's Requirements.

Have a great weekend.
With kind regards,

Glen

Glen Aitken
Engineering Project Administrator

tie limited
Citypoint
65 Haymarket Terrace
Edinburgh EH12 5HD

tel. 

email. Glen.Aitken@tie.ltd.uk
web. www.tie.ltd.uk

The information transmitted is intended only for the person to whom it is addressed and may contain confidential and/or privileged material. If you are not the intended recipient of this e-mail please notify the sender immediately at the email address above, and then delete it.

E-mails sent to and by our staff are monitored for operational and lawful business purposes including assessing compliance with our company rules and system performance. TIE reserves the right to monitor emails sent to or from addresses under its control.

20/12/2007

CEC02085660_0065

No liability is accepted for any harm that may be caused to your systems or data by this e-mail. It is the recipient's responsibility to scan this e-mail and any attachments for computer viruses.

Senders and recipients of e-mail should be aware that under Scottish Freedom of Information legislation and the Data Protection legislation these contents may have to be disclosed to third parties in response to a request.

tie Limited registered in Scotland No. SC230949. Registered office - City Chambers, High Street, Edinburgh, EH1 1YT.

APPENDIX B3

EDINBURGH TRAM

Activity ID	Activity Name	Original Duration	Start	Finish	2008												2009												2010												2011														
					O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D
Edinburgh Tram Tender (updated 11 December 2007)					1077	28-Sep-07	19-Dec-11																																																
Advanced Works Contract					104	01-Oct-07	28-Feb-08	28-Feb-08, Advanced Works Contract Award Advanced Works/Mobilisation Contract, Advanced Works Design and Planning, Advanced Works Procurement of Long Lead Items																																															
161	Award Advanced Works/Mobilisation Contract	0	01-Oct-07*		AWARD CONTRACT, Mobilisation, Commence Phase 1a																																																		
161.1	Advanced Works Design and Planning	150	01-Oct-07*	28-Feb-08																																																			
161.2	Advanced Works Procurement of Long Lead Items	150	01-Oct-07*	28-Feb-08																																																			
Key Dates					992	01-Feb-08	19-Dec-11																																																
170	AWARD CONTRACT	0	01-Feb-08*																																																				
270	Mobilisation	20	01-Feb-08	28-Feb-08																																																			
280	Commence Phase 1a	0	01-Feb-08																																																				
281	Construction Completion Phase 1a Edinburgh Airport to Haymarket	0		30-Aug-10	Construction Completion Phase 1a Edinburgh																																																		
310	Commencement of Revenue Service Phase 1a Edinburgh Airport to Haymarket	0		27-Feb-11	Commencement of Revenue																																																		
311	Construction Completion Phase 1a Haymarket to Newhaven	0		09-Feb-11	Construction Completion Ph																																																		
312.8	Commencement of Revenue Service Phase 1a Haymarket to Newhaven	0		08-Aug-11	Commence																																																		
320	Commence Phase 1b	0	05-Jul-09*		Commence Phase 1b,																																																		
330	Construction Completion Phase 1b	0		22-Jun-11	Construction C																																																		
350	Commencement of Revenue Service Phase 1b	0		19-Dec-11																																																			
Commissioning Phase 1a Edinburgh Airport to Haymarket					167	01-Jul-10	27-Feb-11	27-Feb-11, Commissioning Latest date for first tram on site available for compr System Integration Test; Phase 1a Edinb Test Running and Driver Familiarisation T1 Post Commissioning Test completed; Phase 1a Edinburgh Airport to Haymarket Test Running and Driver familiarisation performance ramp up 1a Airport to Hayma T2 Performance Test completed; Phase 1a Edinburgh Airport to Haymarket Approval of HMRI; Phase 1a Edinburgh Airport to Haymarket Shadow running; Phase 1a Edinburgh Airport to Haymarket T3 Pre-Operations Test Completed; Phase 1a Edinburgh Airport to Haymarket																																															
295	Latest date for first tram on site available for commissioning	0		01-Jul-10																																																			
300	System Integration Test; Phase 1a Edinburgh Airport to Haymarket	30	31-Aug-10	29-Sep-10																																																			
301	Test Running and Driver Familiarisation; Phase 1a Edinburgh Airport to Haymarket	30	30-Sep-10	29-Oct-10																																																			
302	T1 Post Commissioning Test completed; Phase 1a Edinburgh Airport to Haymarket	0		29-Oct-10																																																			
302.1	Test Running and Driver familiarisation performance ramp up 1a Airport to Hayma	30	30-Oct-10	29-Nov-10																																																			
302.2	T2 Performance Test completed; Phase 1a Edinburgh Airport to Haymarket	0		28-Nov-10																																																			
302.3	Approval of HMRI; Phase 1a Edinburgh Airport to Haymarket	0		28-Nov-10																																																			
302.4	Shadow running; Phase 1a Edinburgh Airport to Haymarket	90	29-Nov-10	27-Feb-11																																																			
302.5	T3 Pre-Operations Test Completed; Phase 1a Edinburgh Airport to Haymarket	0		27-Feb-11																																																			
Commissioning Phase 1a Haymarket to Newhaven					128	10-Feb-11	08-Aug-11	08-Aug-11 System Integration Test; Test Running and Driv T1 Post Commissioning Test Running and D T2 Performance Te Approval of HMRI; Shadow ru T3 Pre-Op																																															
312	System Integration Test; Phase 1a Haymarket to Newhaven	30	10-Feb-11	11-Mar-11																																																			
312.1	Test Running and Driver Familiarisation; Phase 1a Haymarket to Newhaven	30	12-Mar-11	10-Apr-11																																																			
312.2	T1 Post Commissioning Test completed; Phase 1a Haymarket to Newhaven	0		10-Apr-11																																																			
312.3	Test Running and Driver familiarisation performance ramp up 1a Haymarket to Ne	30	11-Apr-11	10-May-11																																																			
312.4	T2 Performance Test completed; Phase 1a Haymarket to Newhaven	0		10-May-11																																																			
312.5	Approval of HMRI; Phase 1a Haymarket to Newhaven	0		10-May-11																																																			
312.6	Shadow running; Phase 1a Haymarket to Newhaven	90	11-May-11	08-Aug-11																																																			
312.7	T3 Pre-Operations Test Completed; Phase 1a Haymarket to Newhaven	0		08-Aug-11																																																			
Commissioning Phase 1b					128	23-Jun-11	19-Dec-11	System; Inter Test; Run T1 Post C Test R T2 Per Appro																																															
340	System Integration Test; Phase 1b	30	23-Jun-11	22-Jul-11																																																			
340.1	Test Running and Driver Familiarisation; Phase 1b	30	23-Jul-11	21-Aug-11																																																			
340.2	T1 Post Commissioning Test completed; Phase 1b	0		21-Aug-11																																																			
340.3	Test Running and Driver familiarisation performance ramp up	30	22-Aug-11	20-Sep-11																																																			
340.4	T2 Performance Test completed; Phase 1b	0		20-Sep-11																																																			
340.5	Approval of HMRI; Phase 1b	0		20-Sep-11																																																			
340.6	Shadow running; Phase 1b	90	21-Sep-11	19-Dec-11																																																			
340.7	T3 Pre-Operations Test Completed; Phase 1b	0		19-Dec-11																																																			
M & E Design					148	01-Feb-08	29-Aug-08	29-Aug-08, M & E Design M & E Requirement Definition; Phase Complete; 01-Feb-08* M & E Preliminary Design Phase; M & E Review of Preliminary Design M & E Detail Design Phase M & E Review of Detailed Design																																															
740	M & E Requirement Definition Phase Complete	0		01-Feb-08*																																																			
750	M & E Preliminary Design Phase	60	01-Feb-08	01-Apr-08																																																			
760	M & E Review of Preliminary Design	30	01-Apr-08	01-May-08																																																			
770	M & E Detail Design Phase	90	01-May-08	30-Jul-08																																																			
780	M & E Review of Detailed Design	30	30-Jul-08	29-Aug-08																																																			

Activity ID	Activity Name	Original Duration	Start	Finish	2006												2009												2010												2011														
					O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D
790	M & E Design Freeze	0		29-Aug-08	◆ M & E Design Freeze, 29-Aug-08																																																		
MUDFA					285	05-Nov-07	19-Dec-08	◆ 19-Dec-08, MUDFA																																															
180	MUDFA work area 1 completion	0	31-Oct-08*		◆ MUDFA work area 1 completion,																																																		
190	MUDFA work area 2 completion	0	01-Aug-08*		◆ MUDFA work area 2 completion,																																																		
200	MUDFA work for sub section 1C	0	31-Oct-08*		◆ MUDFA work for sub section 1C,																																																		
210	MUDFA work for sub section 1D	0	19-Dec-08*		◆ MUDFA work for sub section 1D,																																																		
220	MUDFA work area 5	0	05-Nov-07*		◆ MUDFA work area 5,																																																		
230	MUDFA work for sub section 5B	0	11-Apr-08*		◆ MUDFA work for sub section 5B,																																																		
240	MUDFA work for sub section 5C	0	16-May-08*		◆ MUDFA work for sub section 5C,																																																		
260	MUDFA work area 9 completion	0	16-May-08*		◆ MUDFA work area 9 completion,																																																		
SECTION 01 NEWHAVEN ROAD TO HAYMARKET					772	28-Jan-08	09-Feb-11	◆ 09-Feb-11, SECTION 01 NEWHAVEN ROAD TO HAYMARKET																																															
Opening Sequence B (Haymarket to Newhaven Road)					772	28-Jan-08	09-Feb-11	◆ 09-Feb-11, Opening Sequence B (Haymarket to Newhaven Road)																																															
01A Newhaven Road (inc.) to Foot of the Walk (exc.)					752	25-Feb-08	09-Feb-11	◆ 09-Feb-11, 01A Newhaven Road (inc.) to Foot of the Walk (exc.)																																															
E & M Installations					72	28-Oct-10	09-Feb-11	◆ 09-Feb-11, E & M Installations																																															
A3883	Access for visual inspection for E&M wayside installation (01A)	1	28-Oct-10	29-Oct-10	◆ Access for visual inspection for E&M wayside installation (01A)																																																		
A3884	Access for E&M wayside installation (01A)	0	29-Nov-10		◆ Access for E&M wayside installation (01A)																																																		
A3885	Installation of poles and building fixings	22	27-Nov-10	18-Dec-10	◆ Installation of poles and building fixings																																																		
A3890	Overhead Catenary Line	53	19-Dec-10	09-Feb-11	◆ Overhead Catenary Line																																																		
A3898	Access for visual inspection to cable pits for cable laying (01A)	0	28-Oct-10		◆ Access for visual inspection to cable pits for cable laying (01A)																																																		
A3899	Access to cable pits for cable laying (01A)	0	29-Nov-10		◆ Access to cable pits for cable laying (01A)																																																		
A3900	Install Electrical Cables	25	29-Nov-10	23-Dec-10	◆ Install Electrical Cables																																																		
A3910	Install Fibre Optic Cables	25	29-Dec-10	22-Jan-11	◆ Install Fibre Optic Cables																																																		
A3920	Install Signalling Wayside Equipment	25	24-Dec-10	17-Jan-11	◆ Install Signalling Wayside Equipment																																																		
Newhaven Road (inc.) to Ocean Terminal (exc.)					535	07-May-08	17-Jun-10	◆ 17-Jun-10, Newhaven Road (inc.) to Ocean Terminal (exc.)																																															
Lindsay Road Retaining Walls (W1)					176	16-May-08	28-Jan-09	◆ 28-Jan-09, Lindsay Road Retaining Walls (W1)																																															
12000	Issue Construction Drawings	0		18-May-08*	◆ Issue Construction Drawings, 18-May-08*																																																		
5	Wall B Contiguous Bored Piles	100	17-Jun-08	04-Nov-08	◆ Wall B Contiguous Bored Piles																																																		
A1710	Wall A Reinforced Earth	50	05-Nov-08	28-Jan-09	◆ Wall A Reinforced Earth																																																		
Roadworks					291	03-Oct-08	27-Nov-09	◆ 27-Nov-09, Roadworks																																															
11970	Issue Construction Drawings	0		03-Oct-08*	◆ Issue Construction Drawings, 03-Oct-08*																																																		
A1090	CH 0000 to 0300	30	19-Oct-09	27-Nov-09	◆ CH 0000 to 0300																																																		
A1100	CH 0300 to 0700	30	21-May-09	02-Jul-09	◆ CH 0300 to 0700																																																		
A1110	CH 0700 to 0850	175	03-Nov-08	23-Jul-09	◆ CH 0700 to 0850																																																		
Trackwork					302	03-Oct-08	14-Dec-09	◆ 14-Dec-09, Trackwork																																															
11980	Issue Construction Drawings	0		03-Oct-08*	◆ Issue Construction Drawings, 03-Oct-08*																																																		
A1000	CH 0000 to 0265	25	14-Sep-09	16-Oct-09	◆ CH 0000 to 0265																																																		
A1010	CH 0265 to 0425	80	21-May-09	11-Sep-09	◆ CH 0265 to 0425																																																		
A1020	CH 0425 to 0475	35	03-Nov-08	05-Jan-09	◆ CH 0425 to 0475																																																		
A1030	CH 0475 to 0600	40	06-Jan-09	02-Mar-09	◆ CH 0475 to 0600																																																		
A1040	CH 0600 to 0700	55	03-Mar-09	20-May-09	◆ CH 0600 to 0700																																																		
A1050	CH 0700 to 0850	40	18-Oct-09	14-Dec-09	◆ CH 0700 to 0850																																																		
Newhaven Road Tramstop					535	07-May-08	17-Jun-10	◆ 17-Jun-10, Newhaven Road Tramstop																																															
11990	Issue Construction Drawings	0		07-May-08*	◆ Issue Construction Drawings, 07-May-08*																																																		
8	Civil and Building Works	65	19-Oct-09	01-Feb-10	◆ Civil and Building Works																																																		
98	Order REC Supply	0	01-Feb-10		◆ Order REC Supply																																																		
A1680	Deliver and Install Shelter	10	15-Mar-10	29-Mar-10	◆ Deliver and Install Shelter																																																		
A4288	Access for visual inspection for E&M Tram Stop installation (01A Newhaven Road)	0	25-Feb-10		◆ Access for visual inspection for E&M Tram Stop installation (01A Newhaven Road)																																																		
A4289	Access for E&M Tram Stop installation (01A Newhaven Road)	0	29-Mar-10		◆ Access for E&M Tram Stop installation (01A Newhaven Road)																																																		
A4290	Install LV Power Supply and LV Power Equipment	25	29-Mar-10	05-May-10	◆ Install LV Power Supply and LV Power Equipment																																																		
A4300	Install Telecon Equipment	20	05-May-10	03-Jun-10	◆ Install Telecon Equipment																																																		
A4310	Install Station Control Equipment + AFC Equipment	25	05-May-10	10-Jun-10	◆ Install Station Control Equipment + AFC Equipment																																																		
A4315	Package Test Tramstop	5	10-Jun-10	17-Jun-10	◆ Package Test Tramstop																																																		
Leith Sands Sub Station					142	28-Sep-09	19-Apr-10	◆ 19-Apr-10, Leith Sands Sub Station																																															
36	Order REC supply from Scottish Power	0	28-Sep-09		◆ Order REC supply from Scottish Power																																																		

Activity ID	Activity Name	Original Duration	Start	Finish	2008												2009												2010												2011														
					O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D
McDonald / Brunswick Road Ch 950-1250					41	14-Sep-09	09-Nov-09	▼ 09-Nov-09; McDonald / Brunswick Road; Ch 950-1250																																															
1st half					21	14-Sep-09	12-Oct-09	▼ 12-Oct-09; 1st half																																															
A13010	Establish Traffic Management & Temp. Fencing	2	14-Sep-09	15-Sep-09	I Establish Traffic Management & Temp. Fencing																																																		
A13020	Excavate box	2	16-Sep-09	17-Sep-09	I Excavate box																																																		
A13030	Excavate, lay and concrete ducts	3	18-Sep-09	22-Sep-09	I Excavate, lay and concrete ducts																																																		
A13040	Excavate and construct OLE bases	3	18-Sep-09	22-Sep-09	I Excavate and construct OLE bases																																																		
A13050	Place Lower concrete and cure	3	23-Sep-09	25-Sep-09	I Place Lower concrete and cure																																																		
A13060	Set Track (300m)	3	28-Sep-09	30-Sep-09	I Set Track (300m)																																																		
A13070	Place upper concrete and cure	5	01-Oct-09	07-Oct-09	I Place upper concrete and cure																																																		
A13080	Street Surface finishes	3	08-Oct-09	12-Oct-09	I Street Surface finishes																																																		
2nd half					20	13-Oct-09	09-Nov-09	▼ 09-Nov-09; 2nd half																																															
A13410	Excavate box	2	13-Oct-09	14-Oct-09	I Excavate box																																																		
A13420	Excavate, lay and concrete ducts	3	15-Oct-09	19-Oct-09	I Excavate, lay and concrete ducts																																																		
A13430	Excavate and construct OLE bases	3	15-Oct-09	19-Oct-09	I Excavate and construct OLE bases																																																		
A13440	Place Lower concrete and cure	3	20-Oct-09	22-Oct-09	I Place Lower concrete and cure																																																		
A13450	Set Track	3	23-Oct-09	27-Oct-09	I Set Track																																																		
A13460	Place upper concrete and cure	5	28-Oct-09	03-Nov-09	I Place upper concrete and cure																																																		
A13470	Street Surface finishes	3	04-Nov-09	06-Nov-09	I Street Surface finishes																																																		
A13480	Remove fencing and Traffic Management	1	09-Nov-09	09-Nov-09	I Remove fencing and Traffic Management																																																		
Leith Walk Railway Bridge (S18)					0	16-Jul-09	16-Jul-09	▼ 16-Jul-09; Leith Walk Railway Bridge (S18)																																															
26	Existing Structure	0		16-Jul-09	◆ Existing Structure, 16-Jul-09																																																		
Roadworks					287	28-Mar-08	14-May-09	▼ 14-May-09; Roadworks																																															
12160	Issue Construction Drawings	0		28-Mar-08*	◆ Issue Construction Drawings, 28-Mar-08*																																																		
Balfour Street Ch 600-850					39	12-Dec-08	06-Feb-09	▼ 06-Feb-09; Balfour Street; Ch 600-850																																															
A12130	Establish Traffic Management & Temp. Fencing	2	12-Dec-08	15-Dec-08	I Establish Traffic Management & Temp. Fencing																																																		
A12140	Excavate for new channel and kerb line / remove existing kerbs	10	16-Dec-08	12-Jan-09	I Excavate for new channel and kerb line / remove existing kerbs																																																		
A12150	Construct Kerb lines	13	19-Dec-08	20-Jan-09	I Construct Kerb lines																																																		
A12160	Reset Gullies	13	09-Jan-09	27-Jan-09	I Reset Gullies																																																		
A12170	Surface new channel	6	28-Jan-09	04-Feb-09	I Surface new channel																																																		
A12180	Pavement Works	12	21-Jan-09	05-Feb-09	I Pavement Works																																																		
A12190	Street Lighting / Traffic Signals / Road Signs	7	21-Jan-09	29-Jan-09	I Street Lighting / Traffic Signals / Road Signs																																																		
A12200	Remove fencing and Traffic Management	1	08-Feb-09	06-Feb-09	I Remove fencing and Traffic Management																																																		
Pirng / Iona Street Ch 850-950					31	09-Feb-09	23-Mar-09	▼ 23-Mar-09; Pirng / Iona Street Ch 850-950																																															
A12210	Establish Traffic Management & Temp. Fencing	2	09-Feb-09	10-Feb-09	I Establish Traffic Management & Temp. Fencing																																																		
A12220	Excavate for new channel and kerb line / remove existing kerbs	10	11-Feb-09	24-Feb-09	I Excavate for new channel and kerb line / remove existing kerbs																																																		
A12230	Construct Kerb lines	13	15-Feb-09	04-Mar-09	I Construct Kerb lines																																																		
A12240	Reset Gullies	13	23-Feb-09	11-Mar-09	I Reset Gullies																																																		
A12250	Surface new channel	6	12-Mar-09	19-Mar-09	I Surface new channel																																																		
A12260	Pavement Works	12	05-Mar-09	20-Mar-09	I Pavement Works																																																		
A12270	Street Lighting / Traffic Signals / Road Signs	7	05-Mar-09	13-Mar-09	I Street Lighting / Traffic Signals / Road Signs																																																		
A12280	Remove fencing and Traffic Management	1	23-Mar-09	23-Mar-09	I Remove fencing and Traffic Management																																																		
McDonald / Brunswick Road Ch 950-1250					38	24-Mar-09	14-May-09	▼ 14-May-09; McDonald / Brunswick Road Ch 950-1250																																															
A12290	Establish Traffic Management & Temp. Fencing	2	24-Mar-09	25-Mar-09	I Establish Traffic Management & Temp. Fencing																																																		
A12300	Excavate for new channel and kerb line / remove existing kerbs	12	26-Mar-09	13-Apr-09	I Excavate for new channel and kerb line / remove existing kerbs																																																		
A12310	Construct Kerb lines	15	31-Mar-09	21-Apr-09	I Construct Kerb lines																																																		
A12320	Reset Gullies	15	07-Apr-09	28-Apr-09	I Reset Gullies																																																		
A12330	Surface new channel	9	29-Apr-09	12-May-09	I Surface new channel																																																		
A12340	Pavement Works	15	22-Apr-09	13-May-09	I Pavement Works																																																		
A12350	Street Lighting / Traffic Signals / Road Signs	7	22-Apr-09	30-Apr-09	I Street Lighting / Traffic Signals / Road Signs																																																		
A12360	Remove fencing and Traffic Management	1	14-May-09	14-May-09	I Remove fencing and Traffic Management																																																		
Balfour Street Tram Stop					556	28-Jan-08	05-Apr-10	▼ 05-Apr-10; Balfour Street Tram Stop																																															
12170	Issue Construction Drawings	0		28-Jan-08*	◆ Issue Construction Drawings, 28-Jan-08*																																																		
538	Order REC Supply	0		06-Nov-09	◆ Order REC Supply																																																		
Construction					223	19-May-09	05-Apr-10	▼ 05-Apr-10; Construction																																															
590	Civil Engineering And Building Works	65	19-May-09	19-Aug-09	I Civil Engineering And Building Works																																																		

Activity ID	Activity Name	Original Duration	Start	Finish	2008												2009												2010												2011														
					O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D
A2600	Deliver and Install Shelter	10	04-Jan-10	18-Jan-10																																																			
A4478	Access for visual inspection for E&M Tram Stop installation (01B Balfour Street)	0	17-Dec-09																																																				
A4479	Access for E&M Tram Stop installation (01B Balfour Street)	0	18-Jan-10																																																				
A4480	Install LV Power Supply and LV Power Equipment	25	18-Jan-10	22-Feb-10																																																			
A4490	Install Telecom Equipment	20	22-Feb-10	22-Mar-10																																																			
A4500	Install Station Control Equipment + AFC Equipment	25	22-Feb-10	29-Mar-10																																																			
A4510	Package Test Tramstop	5	29-Mar-10	06-Apr-10																																																			
01C McDonald Road (inc.) to Princess Street West (exc.)					757	04-Feb-08	28-Jan-11																																																
E & M Installations					82	02-Jun-10	27-Aug-10																																																
A3843	Access for visual inspection for E&M wayside installation (01C)	0	02-Jun-10																																																				
A3844	Access for E&M wayside installation (01C)	0	02-Jun-10																																																				
A3845	Installation of poles and building fixings	15	24-Jun-10	08-Jul-10																																																			
A3850	Overhead Catenary Line	36	09-Jul-10	13-Aug-10																																																			
A3858	Access for visual inspection to cable pits for cable laying (01C)	0	19-Jul-10																																																				
A3859	Access to cable pits for cable laying (01C)	0	19-Jul-10																																																				
A3860	Install Electrical Cables	20	19-Jul-10	07-Aug-10																																																			
A3870	Install Fibre Optic Cables	20	19-Jul-10	07-Aug-10																																																			
A3880	Install Signaling Wayside Equipment	20	08-Aug-10	27-Aug-10																																																			
McDonald Road (inc.) to Picardy Place (exc.)					577	04-Feb-08	12-May-10																																																
McDonald Road Tram Stop					577	04-Feb-08	12-May-10																																																
12180	Issue Construction Drawings	0		04-Feb-08*																																																			
548	Order REC Supply	0	23-Nov-09																																																				
600	Civil Engineering And Building Works	65	22-Jul-09	24-Nov-09																																																			
A2650	Deliver and Install Shelter	10	08-Feb-10	22-Feb-10																																																			
A2658	Access for visual inspection for E&M Tram Stop installation (01C McDonald Road)	0	21-Jan-10																																																				
A2659	Access for E&M Tram Stop installation (01C McDonald Road)	0	22-Feb-10																																																				
A2670	Install LV Power Supply and LV Power Equipment	25	22-Feb-10	29-Mar-10																																																			
A2673	Install Telecom Equipment	20	29-Mar-10	27-Apr-10																																																			
A2675	Install Station Control Equipment + AFC Equipment	25	29-Mar-10	05-May-10																																																			
A2680	Package Test Tramstop	5	05-May-10	12-May-10																																																			
Trackworks					447	28-Apr-08	02-Feb-10																																																
12190	Issue Construction Drawings	0		28-Apr-08*																																																			
Leith Walk Ch 0-375					74	22-Jul-09	03-Nov-09																																																
A13550	Dummy	50	22-Jul-09	03-Nov-09																																																			
London Road Ch 375-450					51	04-Nov-09	02-Feb-10																																																
A13560	Dummy	40	04-Nov-09	02-Feb-10																																																			
Roadworks					312	28-Apr-08	21-Jul-09																																																
12200	Issue Construction Drawings	0		28-Apr-08*																																																			
Leith Walk Ch 0-375					101	31-Oct-08	26-Mar-09																																																
A13540	Dummy	80	31-Oct-08	26-Mar-09																																																			
London Road Ch 375-450					81	27-Mar-09	21-Jul-09																																																
A13570	Dummy	80	27-Mar-09	21-Jul-09																																																			
Picardy Place (inc.) to St. Andrews Square (exc.)					728	14-Mar-08	26-Jan-11																																																
Trackworks					566	28-Apr-08	21-Jul-10																																																
12210	Issue Construction Drawings	0		28-Apr-08*																																																			
Picardy Place Ch 450-700					81	29-Mar-10	21-Jul-10																																																
Phase 3					42	29-Mar-10	25-May-10																																																
A13640	Dummy	40	29-Mar-10	25-May-10																																																			
Phase 4					39	26-May-10	21-Jul-10																																																
A13650	Dummy	40	26-May-10	21-Jul-10																																																			
York Place Ch 700-850					44	04-Jan-10	04-Mar-10																																																
A13660	Dummy	44	04-Jan-10	04-Mar-10																																																			
York Place Ch 850-1000					45	13-Apr-10	15-Jun-10																																																
A13670	Dummy	44	13-Apr-10	15-Jun-10																																																			
Picardy Place Tram Stop					623	14-Mar-08	26-Aug-10																																																

Activity ID	Activity Name	Original Duration	Start	Finish	2008												2009												2010												2011											
					O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S
12220	Issue Construction Drawings	0		14-Mar-08*	◆ Issue Construction Drawings, 14-Mar-08*																																															
558	Order REC Supply	0	13-Apr-10		◆ Order REC Supply																																															
610	Civil Engineering And Building Works	65	29-Mar-10	30-Jun-10	Civil Engineering And Building Works																																															
A2720	Deliver and Install Shelter	10	26-May-10	09-Jun-10	Deliver and Install Shelter																																															
A4518	Access for visual inspection for E&M Tram Stop installation (01C Picardy Place)	0	11-May-10		◆ Access for visual inspection for E&M Tram Stop installat																																															
A4519	Access for E&M Tram Stop installation (01C Picardy Place)	0	10-Jun-10		◆ Access for E&M Tram Stop installation (01C Picardy																																															
A4520	Install LV Power Supply and LV Power Equipment	25	10-Jun-10	14-Jul-10	Install LV Power Supply and LV Power Equipment																																															
A4530	Install Telecom Equipment	20	15-Jul-10	12-Aug-10	Install Telecom Equipment																																															
A4540	Install Station Control Equipment + AFC Equipment	25	15-Jul-10	19-Aug-10	Install Station Control Equipment + AFC Equi																																															
A4550	Package Test Tramstop	5	20-Aug-10	26-Aug-10	Package Test Tramstop																																															
Roadworks					26-Jan-11, Roadworks																																															
12230	Issue Construction Drawings	0		28-Apr-08*	◆ Issue Construction Drawings, 28-Apr-08*																																															
Picardy Place Ch 450-700					26-Jan-11, Picardy Place Ch																																															
Phase 1					29-Jan-10, Phase 1																																															
A13580	Dummy	20	04-Jan-10	29-Jan-10	Dummy																																															
Phase 2					26-Mar-10, Phase 2																																															
A13590	Dummy	40	01-Feb-10	28-Mar-10	Dummy																																															
Phase 3					25-May-10, Phase 3																																															
A13600	Dummy	42	29-Mar-10	25-May-10	Dummy																																															
Phase 4					21-Jul-10, Phase 4																																															
A13610	Dummy	39	26-May-10	21-Jul-10	Dummy																																															
Phase 5					20-Oct-10, Phase 5																																															
A13620	Dummy	64	22-Jul-10	20-Oct-10	Dummy																																															
Phase 6					26-Jan-11, Phase 6																																															
A13630	Dummy	40	21-Oct-10	26-Jan-11	Dummy																																															
York Place Ch 700-850					12-Apr-10, York Place Ch 700-850																																															
Phase 1					12-Mar-10, Phase 1																																															
A13680	Dummy	50	04-Jan-10	12-Mar-10	Dummy																																															
Phase 2					12-Apr-10, Phase 2																																															
A13690	Dummy	21	15-Mar-10	12-Apr-10	Dummy																																															
York Place Ch 850-1000					21-Jul-10, York Place Ch 850-1000																																															
Phase 1					28-Jun-10, Phase 1																																															
A13700	Dummy	51	13-Apr-10	23-Jun-10	Dummy																																															
Phase 2					21-Jul-10, Phase 2																																															
A13710	Dummy	19	24-Jun-10	21-Jul-10	Dummy																																															
Cathedral SubStation					03-Sep-10, Cathedral SubStation																																															
346	Order REC supply from Scottish Power	0	08-Feb-10		◆ Order REC supply from Scottish Power,																																															
356	Civil Engineering and Building Works	65	01-Mar-10	02-Jun-10	Civil Engineering and Building Works																																															
A2838	Access for visual inspection for E&M substation installation (01C Cathedral)	0	04-May-10		◆ Access for visual inspection for E&M substation installat																																															
A2839	Access for E&M substation installation (01C Cathedral)	0	03-Jun-10		◆ Access for E&M substation installation (01C Cathedr																																															
A5560	Power Infeed from Public Net available inc HV cable	0	03-Jun-10		◆ Power Infeed from Public Net available inc HV cable																																															
A5590	Install LV Power Supply and LV Power Equipment	15	03-Jun-10	23-Jun-10	Install LV Power Supply and LV Power Equipment																																															
A5600	Installation of TPS Equipment	30	17-Jun-10	28-Jul-10	Installation of TPS Equipment																																															
A5610	Install Telecom and Scada	15	08-Jul-10	28-Jul-10	Install Telecom and Scada																																															
A5620	Testing and Commissioning	14	29-Jul-10	18-Aug-10	Testing and Commissioning																																															
A5120	Installation of SIG-interlocking cubicle	10	17-Jun-10	30-Jun-10	Installation of SIG-interlocking cubicle																																															
A5130	Commissioning of SIG-interlocking cubicle	5	30-Aug-10	03-Sep-10	Commissioning of SIG-interlocking cubicle																																															
St. Andrews Square (inc.) to Princes Street West (exc.)					03-Sep-10, St. Andrews Square (inc.) to Pr																																															
Trackworks					27-Nov-09, Trackworks																																															
12240	Issue Construction Drawings	0		28-Apr-08*	◆ Issue Construction Drawings, 28-Apr-08*																																															
Waverley Bridge Ch 1310-1460					30-Oct-09, Waverley Bridge Ch 1310-1460																																															
Phase 2					30-Oct-09, Phase 2																																															
A11650	Establish Traffic Management & Temp. Fencing	2	06-Oct-09	07-Oct-09	Establish Traffic Management & Temp. Fencing																																															
A11660	Excavate box	2	08-Oct-09	09-Oct-09	Excavate box																																															
A11670	Excavate, lay and concrete ducts	3	12-Oct-09	14-Oct-09	Excavate, lay and concrete ducts																																															

Activity ID	Activity Name	Original Duration	Start	Finish	2006												2009												2010												2011																					
					G	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J
A9050	Pavement	25	15-Sep-09	19-Oct-09																																																										
A9050	Rebuild Traffic Islands	15	22-Sep-09	12-Oct-09																																																										
A9080	Street Lighting / Road signs	5	06-Oct-09	12-Oct-09																																																										
A9130	Remove fencing and Traffic Management	1	20-Oct-09	20-Oct-09																																																										
Princes Street Ch 200-0, 1980-1310			127	03-Feb-09	31-Jul-09																																																									
Phase 1			102	03-Feb-09	25-Jun-09																																																									
A13840	Establish Traffic Management & Temp. Fencing	2	03-Feb-09	04-Feb-09																																																										
A13850	Excavate North kerbline	19	05-Feb-09	03-Mar-09																																																										
A13860	Relay North kerbs	48	12-Feb-09	21-Apr-09																																																										
A13870	Reset Gullies	48	19-Feb-09	28-Apr-09																																																										
A13880	Plane out wearing course	10	29-Apr-09	13-May-09																																																										
A13890	Resurface road	7	15-Jun-09	23-Jun-09																																																										
A13900	Pavement (1m strip)	48	19-Feb-09	28-Apr-09																																																										
A13910	White Lines	1	24-Jun-09	24-Jun-09																																																										
A13920	Street Lighting / Road signs	5	22-Apr-09	28-Apr-09																																																										
A13930	Remove fencing and Traffic Management	1	25-Jun-09	25-Jun-09																																																										
Phase 2			127	03-Feb-09	31-Jul-09																																																									
A13940	Establish Traffic Management & Temp. Fencing	2	03-Feb-09	04-Feb-09																																																										
A13950	Excavate South kerbline	19	05-Feb-09	03-Mar-09																																																										
A13960	Relay South kerbs	48	12-Feb-09	21-Apr-09																																																										
A13970	Reset Gullies	48	19-Feb-09	28-Apr-09																																																										
A13980	Plane out wearing course	10	29-Apr-09	13-May-09																																																										
A13990	Resurface road	28	24-Jun-09	29-Jul-09																																																										
A14000	Pavement (1m strip)	48	19-Feb-09	28-Apr-09																																																										
A14010	White Lines	1	30-Jul-09	30-Jul-09																																																										
A14020	Street Lighting / Road signs	5	22-Apr-09	28-Apr-09																																																										
A14030	Remove fencing and Traffic Management	1	31-Jul-09	31-Jul-09																																																										
Trackworks (710m)			339	31-Mar-08	30-Jul-09																																																									
12280	Issue Construction Drawings	0		31-Mar-08																																																										
Lothian Road Junction Ch 440-280			125	03-Feb-09	31-Jul-09																																																									
Phase 2			45	03-Feb-09	05-Apr-09																																																									
1st half			23	03-Feb-09	05-Mar-09																																																									
A8320	Establish Traffic Management & Temp. Fencing	2	03-Feb-09	04-Feb-09																																																										
A8330	Excavate box	3	05-Feb-09	09-Feb-09																																																										
A8340	Excavate, lay and concrete ducts	4	10-Feb-09	13-Feb-09																																																										
A8350	Excavate and construct OLE bases	4	10-Feb-09	13-Feb-09																																																										
A8360	Place Lower concrete and cure	3	16-Feb-09	18-Feb-09																																																										
A8370	Set Track (54m)	2	19-Feb-09	20-Feb-09																																																										
A8380	Place upper concrete and cure	5	23-Feb-09	27-Feb-09																																																										
A8390	Street Surface finishes	4	02-Mar-09	05-Mar-09																																																										
2nd half			22	05-Mar-09	06-Apr-09																																																									
A8410	Excavate box	3	05-Mar-09	10-Mar-09																																																										
A8420	Excavate, lay and concrete ducts	4	11-Mar-09	16-Mar-09																																																										
A8430	Excavate and construct OLE bases	4	11-Mar-09	16-Mar-09																																																										
A8440	Place Lower concrete and cure	3	17-Mar-09	19-Mar-09																																																										
A8450	Set Track	2	20-Mar-09	23-Mar-09																																																										
A8460	Place upper concrete and cure	5	24-Mar-09	30-Mar-09																																																										
A8470	Street Surface finishes	4	31-Mar-09	03-Apr-09																																																										
A8480	Remove fencing and Traffic Management	1	06-Apr-09	06-Apr-09																																																										
Phase 3a			31	05-May-09	17-Jun-09																																																									
1st half			16	05-May-09	27-May-09																																																									
A8590	Establish Traffic Management & Temp. Fencing	2	05-May-09	06-May-09																																																										
A8590	Excavate box	1	07-May-09	07-May-09																																																										
A8700	Excavate, lay and concrete ducts	2	08-May-09	11-May-09																																																										
A8710	Excavate and construct OLE bases	2	08-May-09	11-May-09																																																										

Activity ID	Activity Name	Original Duration	Start	Finish	2006												2009												2010												2011											
					O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S
12310	Issue Construction Drawings	0		31-Mar-08*	◆ Issue Construction Drawings, 31-Mar-08*																																															
	Haymarket Ch 1250-1125	207	05-Jan-09	23-Oct-09	▼ 23-Oct-09, Haymarket Ch 1250-1125																																															
	Phase 1	17	05-Jan-09	27-Jan-09	▼ 27-Jan-09, Phase 1																																															
A6390	Establish Traffic Management & Temp. Fencing	2	05-Jan-09	06-Jan-09	I Establish Traffic Management & Temp. Fencing																																															
A6400	Remove Island surfacing and exc. to formation	4	07-Jan-09	12-Jan-09	I Remove island surfacing and exc. to formation																																															
A6410	Construct Kerb lines	2	13-Jan-09	14-Jan-09	I Construct Kerb lines																																															
A6420	Move Gullies	2	15-Jan-09	16-Jan-09	I Move Gullies																																															
A6430	Sub base	2	19-Jan-09	20-Jan-09	I Sub base																																															
A6440	Roadbase/base course/wearing course/temp ramps	3	21-Jan-09	23-Jan-09	I Roadbase/base course/wearing course/temp ramps																																															
A6450	Pavement Works	5	15-Jan-09	21-Jan-09	I Pavement Works																																															
A6460	White Lines	1	26-Jan-09	26-Jan-09	I White Lines																																															
A6470	Street Lighting / Traffic Signals / Road Signs	5	15-Jan-09	21-Jan-09	I Street Lighting / Traffic Signals / Road Signs																																															
A6475	Remove fencing and Traffic Management	1	27-Jan-09	27-Jan-09	I Remove fencing and Traffic Management																																															
	Phase 2	21	28-Jan-09	25-Feb-09	▼ 25-Feb-09, Phase 2																																															
A6480	Establish Traffic Management & Temp. Fencing	2	28-Jan-09	29-Jan-09	I Establish Traffic Management & Temp. Fencing																																															
A6490	Excavate for new channel and kerb line / remove existing kerbs	2	30-Jan-09	02-Feb-09	I Excavate for new channel and kerb line / remove existing kerbs																																															
A6500	Construct Kerb lines	2	03-Feb-09	04-Feb-09	I Construct Kerb lines																																															
A6510	Reset Gullies	1	05-Feb-09	05-Feb-09	I Reset Gullies																																															
A6520	Surface new channel	1	06-Feb-09	06-Feb-09	I Surface new channel																																															
A6540	Pavement Works	15	05-Feb-09	25-Feb-09	I Pavement Works																																															
A6550	White Lines	1	09-Feb-09	09-Feb-09	I White Lines																																															
A6560	Street Lighting / Traffic Signals / Road Signs	3	05-Feb-09	09-Feb-09	I Street Lighting / Traffic Signals / Road Signs																																															
A6565	Remove fencing and Traffic Management	1	12-Feb-09	12-Feb-09	I Remove fencing and Traffic Management																																															
	Phase 4a	23	30-Mar-09	29-Apr-09	▼ 29-Apr-09, Phase 4a																																															
A6730	Establish Traffic Management & Temp. Fencing	2	30-Mar-09	31-Mar-09	I Establish Traffic Management & Temp. Fencing																																															
A6740	Remove Island surfacing and exc. to formation	5	01-Apr-09	07-Apr-09	I Remove island surfacing and exc. to formation																																															
A6750	Construct Kerb lines	4	08-Apr-09	14-Apr-09	I Construct Kerb lines																																															
A6760	Move Gullies	2	15-Apr-09	16-Apr-09	I Move Gullies																																															
A6770	Sub base	3	17-Apr-09	21-Apr-09	I Sub base																																															
A6775	Plane off wearing course	1	22-Apr-09	22-Apr-09	I Plane off wearing course																																															
A6780	Roadbase/base course/wearing course/temp ramps	3	23-Apr-09	27-Apr-09	I Roadbase/base course/wearing course/temp ramps																																															
A6790	Pavement Works	6	15-Apr-09	22-Apr-09	I Pavement Works																																															
A6800	White Lines	1	28-Apr-09	28-Apr-09	I White Lines																																															
A6810	Street Lighting / Traffic Signals / Road Signs	7	15-Apr-09	23-Apr-09	I Street Lighting / Traffic Signals / Road Signs																																															
A6815	Remove fencing and Traffic Management	1	29-Apr-09	29-Apr-09	I Remove fencing and Traffic Management																																															
	Phase 4b	20	30-Apr-09	28-May-09	▼ 28-May-09, Phase 4b																																															
A6820	Establish Traffic Management & Temp. Fencing	2	30-Apr-09	01-May-09	I Establish Traffic Management & Temp. Fencing																																															
A6830	Remove Island surfacing and exc. to formation	1	05-May-09	05-May-09	I Remove island surfacing and exc. to formation																																															
A6840	Construct Kerb lines	4	06-May-09	11-May-09	I Construct Kerb lines																																															
A6850	Move Gullies	2	12-May-09	13-May-09	I Move Gullies																																															
A6860	Sub base	3	14-May-09	18-May-09	I Sub base																																															
A6870	Plane off wearing course	1	19-May-09	19-May-09	I Plane off wearing course																																															
A6880	Roadbase/base course/wearing course/temp ramps	3	20-May-09	22-May-09	I Roadbase/base course/wearing course/temp ramps																																															
A6890	Pavement Works	12	12-May-09	28-May-09	I Pavement Works																																															
A6900	White Lines	1	26-May-09	26-May-09	I White Lines																																															
A6910	Street Lighting / Traffic Signals / Road Signs	7	12-May-09	20-May-09	I Street Lighting / Traffic Signals / Road Signs																																															
A6915	Remove fencing and Traffic Management	1	27-May-09	27-May-09	I Remove fencing and Traffic Management																																															
	Phase 6b	49	17-Jul-09	24-Sep-09	▼ 24-Sep-09, Phase 6b																																															
A7240	Establish Traffic Management & Temp. Fencing	2	17-Jul-09	20-Jul-09	I Establish Traffic Management & Temp. Fencing																																															
A7250	Excavate for new channel and kerb line / remove existing kerbs	2	21-Jul-09	22-Jul-09	I Excavate for new channel and kerb line / remove existing kerbs																																															
A7260	Construct Kerb lines	5	23-Jul-09	29-Jul-09	I Construct Kerb lines																																															
A7270	Reset Gullies	5	24-Jul-09	30-Jul-09	I Reset Gullies																																															
A7280	Surface new channel	2	31-Jul-09	07-Sep-09	I Surface new channel																																															
A7290	Pavement Works	15	30-Jul-09	23-Sep-09	I Pavement Works																																															
A7310	Street Lighting / Traffic Signals / Road Signs	7	30-Jul-09	11-Sep-09	I Street Lighting / Traffic Signals / Road Signs																																															

Activity ID	Activity Name	Original Duration	Start	Finish	2008												2009												2010												2011														
					O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D
A7315	Remove fencing and Traffic Management	1	24-Sep-09	24-Sep-09																																																	I: Remove fencing and Traffic Management		
Phase 7																																																					▼ 23-Oct-09, Phase 7		
A7320	Establish Traffic Management & Temp. Fencing	2	05-Oct-09	06-Oct-09																																																	I: Establish Traffic Management & Temp. Fencing		
A7330	Replace north junction kerb line	6	07-Oct-09	14-Oct-09																																																	I: Replace north junction kerb line		
A7340	Rebuild splitter island	6	15-Oct-09	22-Oct-09																																																	I: Rebuild splitter island		
A7350	White Lines / Traffic Signals / Road Signs	4	07-Oct-09	12-Oct-09																																																	I: White Lines / Traffic Signals / Road Signs		
A7355	Remove fencing and Traffic Management	1	23-Oct-09	23-Oct-09																																																	I: Remove fencing and Traffic Management		
Torphicken Ch 1125-940																																																					▼ 09-Mar-10, Torphicken Ch 1125-940		
Phase 3																																																					▼ 09-Mar-10, Phase 3		
North Pavement																																																					▼ 20-Jan-10, North Pavement		
A7680	Establish Traffic Management & Temp. Fencing	2	04-Jan-10	05-Jan-10																																																	I: Establish Traffic Management & Temp. Fencing		
A7690	Replace north kerb line	10	05-Jan-10	19-Jan-10																																																	I: Replace north kerb line		
A7695	Remove fencing and Traffic Management	1	20-Jan-10	20-Jan-10																																																	I: Remove fencing and Traffic Management		
South Pavement																																																					▼ 09-Feb-10, South Pavement		
A7700	Establish Traffic Management & Temp. Fencing	2	21-Jan-10	22-Jan-10																																																	I: Establish Traffic Management & Temp. Fencing		
A7710	Excavate for new channel and kerb line / remove existing kerbs	2	25-Jan-10	26-Jan-10																																																	I: Excavate for new channel and kerb line / remove existing kerbs		
A7720	Construct Kerb lines	3	27-Jan-10	29-Jan-10																																																	I: Construct Kerb lines		
A7730	Reset Gullies	2	01-Feb-10	02-Feb-10																																																	I: Reset Gullies		
A7740	Surface new channel	1	03-Feb-10	03-Feb-10																																																	I: Surface new channel		
A7750	Pavement Works	7	01-Feb-10	09-Feb-10																																																	I: Pavement Works		
A7760	Street Lighting / Traffic Signals / Road Signs	3	01-Feb-10	03-Feb-10																																																	I: Street Lighting / Traffic Signals / Road Signs		
A7765	Remove fencing and Traffic Management	1	04-Feb-10	04-Feb-10																																																	I: Remove fencing and Traffic Management		
Splitter Island																																																					▼ 09-Mar-10, Splitter Island		
A7770	Establish Traffic Management & Temp. Fencing	2	05-Feb-10	08-Feb-10																																																	I: Establish Traffic Management & Temp. Fencing		
A7780	Excavate for new channel and kerb line / remove existing kerbs	2	09-Feb-10	10-Feb-10																																																	I: Excavate for new channel and kerb line / remove existing kerbs		
A7790	Construct Kerb lines	4	10-Feb-10	15-Feb-10																																																	I: Construct Kerb lines		
A7800	Reset Gullies	4	11-Feb-10	16-Feb-10																																																	I: Reset Gullies		
A7810	Surface new channel	1	17-Feb-10	17-Feb-10																																																	I: Surface new channel		
A7820	Pavement Works	16	16-Feb-10	09-Mar-10																																																	I: Pavement Works		
A7830	Street Lighting / Traffic Signals / Road Signs	3	16-Feb-10	18-Feb-10																																																	I: Street Lighting / Traffic Signals / Road Signs		
A7835	Remove fencing and Traffic Management	1	25-Feb-10	25-Feb-10																																																	I: Remove fencing and Traffic Management		
West Maidland Ch 940-850																																																					▼ 24-Mar-10, West Maidland Ch 940-850		
Phase 1																																																					▼ 24-Mar-10, Phase 1		
South Pavement																																																					▼ 12-Mar-10, South Pavement		
A7840	Establish Traffic Management & Temp. Fencing	2	26-Feb-10	01-Mar-10																																																	I: Establish Traffic Management & Temp. Fencing		
A7850	Excavate for new channel and kerb line / remove existing kerbs	2	02-Mar-10	03-Mar-10																																																	I: Excavate for new channel and kerb line / remove existing kerbs		
A7860	Construct Kerb lines	4	03-Mar-10	08-Mar-10																																																	I: Construct Kerb lines		
A7870	Reset Gullies	4	04-Mar-10	09-Mar-10																																																	I: Reset Gullies		
A7880	Surface new channel	2	10-Mar-10	11-Mar-10																																																	I: Surface new channel		
A7885	Remove fencing and Traffic Management	1	12-Mar-10	12-Mar-10																																																	I: Remove fencing and Traffic Management		
North Pavement																																																					▼ 24-Mar-10, North Pavement		
A7890	Establish Traffic Management & Temp. Fencing	2	15-Mar-10	16-Mar-10																																																	I: Establish Traffic Management & Temp. Fencing		
A7900	Excavate for new channel and kerb line / remove existing kerbs	1	17-Mar-10	17-Mar-10																																																	I: Excavate for new channel and kerb line / remove existing kerbs		
A7910	Construct Kerb lines	2	18-Mar-10	19-Mar-10																																																	I: Construct Kerb lines		
A7920	Reset Gullies	1	22-Mar-10	22-Mar-10																																																	I: Reset Gullies		
A7930	Surface new channel	1	23-Mar-10	23-Mar-10																																																	I: Surface new channel		
A7935	Remove fencing and Traffic Management	1	24-Mar-10	24-Mar-10																																																	I: Remove fencing and Traffic Management		
Shandwick Ch 850-440																																																					▼ 27-Nov-09, Shandwick Ch 850-440		
Phase 1																																																					▼ 27-Nov-09, Phase 1		
A8190	Establish Traffic Management & Temp. Fencing	2	07-Sep-09	09-Sep-09																																																	I: Establish Traffic Management & Temp. Fencing		
A8190	Excavate for new channel and kerb line / remove existing kerbs	18	09-Sep-09	02-Oct-09																																																	I: Excavate for new channel and kerb line / remove existing kerbs		
A8200	Construct Kerb lines	23	14-Sep-09	14-Oct-09																																																	I: Construct Kerb lines		
A8210	Reset Gullies	15	28-Sep-09	16-Oct-09																																																	I: Reset Gullies		
A8220	Surface new channel	9	19-Oct-09	29-Oct-09																																																	I: Surface new channel		
A8230	Pavement Works	31	15-Oct-09	26-Nov-09																																																	I: Pavement Works		

CEC02085660_0086

Activity ID	Activity Name	Original Duration	Start	Finish	2008												2009												2010												2011																																																														
					O N D J F M A M J J A S O N D												O N D J F M A M J J A S O N D												O N D J F M A M J J A S O N D												O N D J F M A M J J A S O N D																																																														
A8240	Street Lighting / Traffic Signals / Road Signs	7	15-Oct-09	23-Oct-09																																																	B: Street Lighting / Traffic Signals / Road Signs																																																		
A8245	Remove fencing and Traffic Management	1	27-Nov-09	27-Nov-09																																																	Remove fencing and Traffic Management																																																		
Trackwork		542	31-Mar-09	16-May-10																																																	18-May-10, Trackwork																																																		
12320	Issue Construction Drawings	0		31-Mar-09*																																																	◆ Issue Construction Drawings, 31-Mar-09*																																																		
Haymarket Ch 1250-1125					163	12-Feb-09	02-Oct-09																																																	02-Oct-09, Haymarket Ch 1250-1125																																															
Phase 3					31	13-Feb-09	27-Mar-09																																																	27-Mar-09, Phase 3																																															
1st half					16	13-Feb-09	06-Mar-09																																																	06-Mar-09, 1st half																																															
A6570	Establish Traffic Management & Temp. Fencing	2	13-Feb-09	16-Feb-09																																																	Establish Traffic Management & Temp. Fencing																																																		
A6580	Excavate box	1	17-Feb-09	17-Feb-09																																																	Excavate box																																																		
A6590	Excavate, lay and concrete ducts	2	18-Feb-09	19-Feb-09																																																	Excavate, lay and concrete ducts																																																		
A6600	Excavate and construct OLE bases	2	18-Feb-09	19-Feb-09																																																	Excavate and construct OLE bases																																																		
A6610	Place Lower concrete and cure	3	20-Feb-09	24-Feb-09																																																	Place Lower concrete and cure																																																		
A6620	Set Track (54m)	1	25-Feb-09	25-Feb-09																																																	Set Track (54m)																																																		
A6630	Place upper concrete and cure	5	26-Feb-09	04-Mar-09																																																	Place upper concrete and cure																																																		
A6640	Street Surface finishes	2	06-Mar-09	06-Mar-09																																																	Street Surface finishes																																																		
2nd half					15	09-Mar-09	27-Mar-09																																																	27-Mar-09, 2nd half																																															
A6650	Excavate box	1	09-Mar-09	09-Mar-09																																																	Excavate box																																																		
A6660	Excavate, lay and concrete ducts	2	10-Mar-09	11-Mar-09																																																	Excavate, lay and concrete ducts																																																		
A6670	Excavate and construct OLE bases	2	10-Mar-09	11-Mar-09																																																	Excavate and construct OLE bases																																																		
A6680	Place Lower concrete and cure	3	12-Mar-09	16-Mar-09																																																	Place Lower concrete and cure																																																		
A6690	Set Track	1	17-Mar-09	17-Mar-09																																																	Set Track																																																		
A6700	Place upper concrete and cure	5	18-Mar-09	24-Mar-09																																																	Place upper concrete and cure																																																		
A6710	Street Surface finishes	2	25-Mar-09	26-Mar-09																																																	Street Surface finishes																																																		
A6720	Remove fencing and Traffic Management	1	27-Mar-09	27-Mar-09																																																	Remove fencing and Traffic Management																																																		
Phase 5					30	04-Jun-09	16-Jul-09																																																	16-Jul-09, Phase 5																																															
1st half					16	04-Jun-09	25-Jun-09																																																	25-Jun-09, 1st half																																															
A6920	Establish Traffic Management & Temp. Fencing	2	04-Jun-09	05-Jun-09																																																	Establish Traffic Management & Temp. Fencing																																																		
A6940	Excavate box	1	08-Jun-09	08-Jun-09																																																	Excavate box																																																		
A6950	Excavate, lay and concrete ducts	2	09-Jun-09	10-Jun-09																																																	Excavate, lay and concrete ducts																																																		
A6960	Excavate and construct OLE bases	2	09-Jun-09	10-Jun-09																																																	Excavate and construct OLE bases																																																		
A6970	Place Lower concrete and cure	3	11-Jun-09	15-Jun-09																																																	Place Lower concrete and cure																																																		
A6980	Set Track (54m)	1	16-Jun-09	16-Jun-09																																																	Set Track (54m)																																																		
A6990	Place upper concrete and cure	5	17-Jun-09	23-Jun-09																																																	Place upper concrete and cure																																																		
A7000	Street Surface finishes	2	24-Jun-09	25-Jun-09																																																	Street Surface finishes																																																		
2nd half					14	23-Jun-09	16-Jul-09																																																	16-Jul-09, 2nd half																																															
A7010	Excavate box	1	26-Jun-09	26-Jun-09																																																	Excavate box																																																		
A7020	Excavate, lay and concrete ducts	2	29-Jun-09	30-Jun-09																																																	Excavate, lay and concrete ducts																																																		
A7030	Excavate and construct OLE bases	2	29-Jun-09	30-Jun-09																																																	Excavate and construct OLE bases																																																		
A7040	Place Lower concrete and cure	3	01-Jul-09	03-Jul-09																																																	Place Lower concrete and cure																																																		
A7050	Set Track	1	06-Jul-09	06-Jul-09																																																	Set Track																																																		
A7060	Place upper concrete and cure	5	07-Jul-09	13-Jul-09																																																	Place upper concrete and cure																																																		
A7070	Street Surface finishes	2	14-Jul-09	15-Jul-09																																																	Street Surface finishes																																																		
A7075	Remove fencing and Traffic Management	1	16-Jul-09	16-Jul-09																																																	Remove fencing and Traffic Management																																																		
Phase 6a					55	17-Jul-09	02-Oct-09																																																	02-Oct-09, Phase 6a																																															
1st half					40	17-Jul-09	11-Sep-09																																																	11-Sep-09, 1st half																																															
A7080	Establish Traffic Management & Temp. Fencing	2	17-Jul-09	20-Jul-09																																																	Establish Traffic Management & Temp. Fencing																																																		
A7100	Excavate box	1	21-Jul-09	21-Jul-09																																																	Excavate box																																																		
A7110	Excavate, lay and concrete ducts	2	22-Jul-09	23-Jul-09																																																	Excavate, lay and concrete ducts																																																		
A7120	Excavate and construct OLE bases	2	22-Jul-09	23-Jul-09																																																	Excavate and construct OLE bases																																																		
A7130	Place Lower concrete and cure	3	24-Jul-09	28-Jul-09																																																	Place lower concrete and cure																																																		
A7140	Set Track (54m)	1	29-Jul-09	29-Jul-09																																																	Set Track (54m)																																																		
A7150	Place upper concrete and cure	5	30-Jul-09	09-Sep-09																																																	Place upper concrete and cure																																																		
A7160	Street Surface finishes	2	10-Sep-09	11-Sep-09																																																	Street Surface finishes																																																		
2nd half					15	14-Sep-09	02-Oct-09																																																	02-Oct-09, 2nd half																																															
A7170	Excavate box	1	14-Sep-09	14-Sep-09																																																	Excavate box																																																		

Activity ID	Activity Name	Original Duration	Start	Finish	2008												2009												2010												2011																																																											
					O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D																																													
A7180	Excavate, lay and concrete ducts	2	15-Sep-09	16-Sep-09																																																	Excavate, lay and concrete ducts																																															
A7190	Excavate and construct OLE bases	2	15-Sep-09	16-Sep-09																																																	Excavate and construct OLE bases																																															
A7200	Place Lower concrete and cure	3	17-Sep-09	21-Sep-09																																																	Place Lower concrete and cure																																															
A7210	Set Track	1	22-Sep-09	22-Sep-09																																																	Set Track																																															
A7220	Place upper concrete and cure	5	23-Sep-09	29-Sep-09																																																	Place upper concrete and cure																																															
A7230	Street Surface finishes	2	30-Sep-09	01-Oct-09																																																	Street Surface finishes																																															
A7235	Remove fencing and Traffic Management	1	02-Oct-09	02-Oct-09																																																	Remove fencing and Traffic Management																																															
Torphichen Ch 1125-940		169	30-Mar-09	16-Nov-09																																																	16-Nov-09, Torphichen Ch 1125-940																																															
Phase 1		47	30-Mar-09	03-Jun-09																																																	03-Jun-09, Phase 1																																															
1st half		24	30-Mar-09	30-Apr-09																																																	30-Apr-09, 1st half																																															
A7360	Establish Traffic Management & Temp. Fencing	2	30-Mar-09	31-Mar-09																																																	Establish Traffic Management & Temp. Fencing																																															
A7360	Excavate box	3	01-Apr-09	03-Apr-09																																																	Excavate box																																															
A7390	Excavate, lay and concrete ducts	4	06-Apr-09	09-Apr-09																																																	Excavate, lay and concrete ducts																																															
A7400	Excavate and construct OLE bases	4	06-Apr-09	09-Apr-09																																																	Excavate and construct OLE bases																																															
A7410	Place Lower concrete and cure	3	13-Apr-09	15-Apr-09																																																	Place Lower concrete and cure																																															
A7420	Set Track (145m)	2	18-Apr-09	17-Apr-09																																																	Set Track (145m)																																															
A7430	Place upper concrete and cure	5	20-Apr-09	24-Apr-09																																																	Place upper concrete and cure																																															
A7440	Street Surface finishes	4	27-Apr-09	30-Apr-09																																																	Street Surface finishes																																															
2nd half		23	01-May-09	03-Jun-09																																																	03-Jun-09, 2nd half																																															
A7450	Excavate box	3	01-May-09	06-May-09																																																	Excavate box																																															
A7460	Excavate, lay and concrete ducts	4	07-May-09	12-May-09																																																	Excavate, lay and concrete ducts																																															
A7470	Excavate and construct OLE bases	4	07-May-09	12-May-09																																																	Excavate and construct OLE bases																																															
A7480	Place Lower concrete and cure	3	13-May-09	15-May-09																																																	Place Lower concrete and cure																																															
A7490	Set Track	2	18-May-09	19-May-09																																																	Set Track																																															
A7500	Place upper concrete and cure	5	20-May-09	27-May-09																																																	Place upper concrete and cure																																															
A7510	Street Surface finishes	4	28-May-09	02-Jun-09																																																	Street Surface finishes																																															
A7515	Remove fencing and Traffic Management	1	03-Jun-09	03-Jun-09																																																	Remove fencing and Traffic Management																																															
Phase 2		31	05-Oct-09	16-Nov-09																																																	16-Nov-09, Phase 2																																															
1st half		16	05-Oct-09	26-Oct-09																																																	26-Oct-09, 1st half																																															
A7520	Establish Traffic Management & Temp. Fencing	2	05-Oct-09	06-Oct-09																																																	Establish Traffic Management & Temp. Fencing																																															
A7540	Excavate box	1	07-Oct-09	07-Oct-09																																																	Excavate box																																															
A7550	Excavate, lay and concrete ducts	2	08-Oct-09	09-Oct-09																																																	Excavate, lay and concrete ducts																																															
A7560	Excavate and construct OLE bases	2	08-Oct-09	09-Oct-09																																																	Excavate and construct OLE bases																																															
A7570	Place Lower concrete and cure	3	12-Oct-09	14-Oct-09																																																	Place Lower concrete and cure																																															
A7580	Set Track (40m)	1	15-Oct-09	15-Oct-09																																																	Set Track (40m)																																															
A7590	Place upper concrete and cure	5	16-Oct-09	22-Oct-09																																																	Place upper concrete and cure																																															
A7600	Street Surface finishes	2	23-Oct-09	26-Oct-09																																																	Street Surface finishes																																															
2nd half		15	27-Oct-09	16-Nov-09																																																	16-Nov-09, 2nd half																																															
A7610	Excavate box	1	27-Oct-09	27-Oct-09																																																	Excavate box																																															
A7620	Excavate, lay and concrete ducts	2	28-Oct-09	29-Oct-09																																																	Excavate, lay and concrete ducts																																															
A7630	Excavate and construct OLE bases	2	28-Oct-09	29-Oct-09																																																	Excavate and construct OLE bases																																															
A7640	Place Lower concrete and cure	3	30-Oct-09	03-Nov-09																																																	Place Lower concrete and cure																																															
A7650	Set Track	1	04-Nov-09	04-Nov-09																																																	Set Track																																															
A7660	Place upper concrete and cure	5	05-Nov-09	11-Nov-09																																																	Place upper concrete and cure																																															
A7670	Street Surface finishes	2	12-Nov-09	13-Nov-09																																																	Street Surface finishes																																															
A7675	Remove fencing and Traffic Management	1	16-Nov-09	16-Nov-09																																																	Remove fencing and Traffic Management																																															
West Maitland Ch 940-850		39	25-Mar-10	18-May-10																																																	18-May-10, West Maitland Ch 940-850																																															
Phases 2 & 3		39	25-Mar-10	18-May-10																																																	18-May-10, Phases 2 & 3																																															
1st half		20	25-Mar-10	21-Apr-10																																																	21-Apr-10, 1st half																																															
A7940	Establish Traffic Management & Temp. Fencing	2	25-Mar-10	26-Mar-10																																																	Establish Traffic Management & Temp. Fencing																																															
A7960	Excavate box	2	29-Mar-10	30-Mar-10																																																	Excavate box																																															
A7970	Excavate, lay and concrete ducts	3	31-Mar-10	05-Apr-10																																																	Excavate, lay and concrete ducts																																															
A7980	Excavate and construct OLE bases	3	31-Mar-10	05-Apr-10																																																	Excavate and construct OLE bases																																															
A7990	Place Lower concrete and cure	3	05-Apr-10	08-Apr-10																																																	Place Lower concrete and cure																																															
A8000	Set Track (90m)	1	09-Apr-10	09-Apr-10																																																	Set Track (90m)																																															

Activity ID	Activity Name	Original Duration	Start	Finish	2008												2009												2010												2011															
					O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	
A4930	Install Telecon Equipment	20	05-Apr-11	03-May-11																																																	<input type="checkbox"/>	Install Telecon Equip		
A4940	Install Station Control Equipment + AFC Equipment	25	05-Apr-11	10-May-11																																																	<input type="checkbox"/>	Install Station Control		
A4950	Package Test Tramstop	5	11-May-11	17-May-11																																																	<input type="checkbox"/>	Package Test Tram		
West Granton Avenue (exc.) to Caroline Park (inc.)					831	07-Jan-08	12-Apr-11																																																	12-Apr-11, West Granton
Trackwork (670m)					605	25-Mar-08	11-Aug-10																																																	11-Aug-10, Trackwork (670m)
12800	Issue Construction Drawings	0		25-Mar-08*																																																	<input type="checkbox"/>	Issue Construction Drawings, 25-Mar-08*		
1279	CBM - Ducts	22	23-Apr-10	25-May-10																																																	<input type="checkbox"/>	CBM - Ducts		
1289	Track laying	14	26-May-10	15-Jun-10																																																	<input type="checkbox"/>	Track laying		
1299	Track Finishes	26	16-Jun-10	21-Jul-10																																																	<input type="checkbox"/>	Track Finishes		
1309	Road Crossings	20	16-Jun-10	13-Jul-10																																																	<input type="checkbox"/>	Road Crossings		
1319	Fencing	14	22-Jul-10	11-Aug-10																																																	<input type="checkbox"/>	Fencing		
293	OLE Foundations - Drainage	27	16-Mar-10	22-Apr-10																																																	<input type="checkbox"/>	OLE Foundations - Drainage		
670	Bulk Excavation - Subbase	16	18-Feb-10	15-Mar-10																																																	<input type="checkbox"/>	Bulk Excavation - Subbase		
Caroline Park Tram Stop					831	07-Jan-08	12-Apr-11																																																	12-Apr-11, Caroline Park
12810	Issue Construction Drawings	0		07-Jan-08*																																																	<input type="checkbox"/>	Issue Construction Drawings, 07-Jan-08*		
195	Civil Engineering and Building Works	65	16-Jun-10	15-Sep-10																																																	<input type="checkbox"/>	Civil Engineering and Building Works		
618	Order REC Supply	0	12-Nov-10																																																		<input type="checkbox"/>	Order REC Supply		
A2960	Deliver and Install Shelter	10	10-Jan-11	24-Jan-11																																																	<input type="checkbox"/>	Deliver and Install Shelter		
A4953	Access for visual inspection for E&M Tram Stop installation (03B Caroline Park)	0	23-Dec-10																																																		<input type="checkbox"/>	Access for visual inspection for E&M Tram Stop installation (03B Caroline Park)		
A4959	Access for E&M Tram Stop installation (03B Caroline Park)	0	24-Jan-11																																																		<input type="checkbox"/>	Access for E&M Tram Stop installation (03B Caroline Park)		
A4960	Install LV Power Supply and LV Power Equipment	25	24-Jan-11	28-Feb-11																																																	<input type="checkbox"/>	Install LV Power Supply and LV Power Equipment		
A4970	Install Telecon Equipment	20	28-Feb-11	28-Mar-11																																																	<input type="checkbox"/>	Install Telecon Equipment		
A4980	Install Station Control Equipment + AFC Equipment	25	28-Feb-11	05-Apr-11																																																	<input type="checkbox"/>	Install Station Control Equipment + AFC Equipment		
A4990	Package Test Tramstop	5	05-Apr-11	12-Apr-11																																																	<input type="checkbox"/>	Package Test Tramstop		
Granton Mains Substation					134	12-Apr-10	19-Oct-10																																																	19-Oct-10, Granton Mains Substation
385	Order REC supply from Scottish Power	0	12-Apr-10																																																		<input type="checkbox"/>	Order REC supply from Scottish Power		
395	Civil Engineering and Building Works	65	04-May-10	04-Aug-10																																																	<input type="checkbox"/>	Civil Engineering and Building Works		
A2988	Access for visual inspection for E&M Substation installation (03B Granton Mains)	0	05-Jul-10																																																		<input type="checkbox"/>	Access for visual inspection for E&M Substation installation (03B Granton Mains)		
A2989	Access for E&M Substation installation (03B Granton Mains)	0	05-Aug-10																																																		<input type="checkbox"/>	Access for E&M Substation installation (03B Granton Mains)		
A5730	Power Infeed from Public Net available inc HV cable	0	05-Aug-10																																																		<input type="checkbox"/>	Power Infeed from Public Net available inc HV cable		
A5740	Install LV Power Supply and LV Power Equipment	15	05-Aug-10	25-Aug-10																																																	<input type="checkbox"/>	Install LV Power Supply and LV Power Equipment		
A5750	Installation of TPS Equipment	30	19-Aug-10	29-Sep-10																																																	<input type="checkbox"/>	Installation of TPS Equipment		
A5760	Install Telecom and Scada	15	09-Sep-10	29-Sep-10																																																	<input type="checkbox"/>	Install Telecom and Scada		
A5770	Testing and Commissioning	14	30-Sep-10	19-Oct-10																																																	<input type="checkbox"/>	Testing and Commissioning		
03C Caroline Park (exc.) to Granton Square (inc.)					759	25-Feb-08	07-Mar-11																																																	07-Mar-11, 03C Caroline Park
E & M Installations					46	09-Aug-10	12-Oct-10																																																	12-Oct-10, E & M Installations
A4003	Access for visual inspection for E&M wayside installation (03C)	0	09-Aug-10																																																		<input type="checkbox"/>	Access for visual inspection for E&M wayside installation (03C)		
A4004	Access for E&M wayside installation (03C)	0	31-Aug-10																																																		<input type="checkbox"/>	Access for E&M wayside installation (03C)		
A4005	Installation of poles and building fixings	9	31-Aug-10	08-Sep-10																																																	<input type="checkbox"/>	Installation of poles and building fixings		
A4010	Overhead Catenary Line	22	09-Sep-10	30-Sep-10																																																	<input type="checkbox"/>	Overhead Catenary Line		
A4018	Access for visual inspection to cable pits for cable laying (03C)	0	28-Aug-10																																																		<input type="checkbox"/>	Access for visual inspection to cable pits for cable laying (03C)		
A4019	Access to cable pits for cable laying (03C)	0	19-Sep-10																																																		<input type="checkbox"/>	Access to cable pits for cable laying (03C)		
A4020	Install Electrical Cables	12	19-Sep-10	30-Sep-10																																																	<input type="checkbox"/>	Install Electrical Cables		
A4030	Install Fibre Optic Cables	12	19-Sep-10	30-Sep-10																																																	<input type="checkbox"/>	Install Fibre Optic Cables		
A4040	Install Signalling Wayside Equipment	12	01-Oct-10	12-Oct-10																																																	<input type="checkbox"/>	Install Signalling Wayside Equipment		
Caroline Park (exc.) to Granton Waterfront (inc.)					763	04-Mar-08	07-Mar-11																																																	07-Mar-11, Caroline Park
Granton Waterfront Tram Stop					763	04-Mar-08	07-Mar-11																																																	07-Mar-11, Granton Waterfront
12620	Issue Construction Drawings	0		04-Mar-08*																																																	<input type="checkbox"/>	Issue Construction Drawings, 04-Mar-08*		
185	Civil Engineering and Building Works	65	02-Mar-10	03-Jun-10																																																	<input type="checkbox"/>	Civil Engineering and Building Works		
608	Order REC Supply	0	08-Oct-10																																																		<input type="checkbox"/>	Order REC Supply		
A2920	Deliver and Install Shelter	10	19-Nov-10	06-Dec-10																																																	<input type="checkbox"/>	Deliver and Install Shelter		
A4998	Access for visual inspection for E&M Tram Stop installation (03C Granton Waterfront)	0	04-Nov-10																																																		<input type="checkbox"/>	Access for visual inspection for E&M Tram Stop installation (03C Granton Waterfront)		
A4999	Access for E&M Tram Stop installation (03C Granton Waterfront)	0	05-Dec-10																																																		<input type="checkbox"/>	Access for E&M Tram Stop installation (03C Granton Waterfront)		
A5000	Install LV Power Supply and LV Power Equipment	25	05-Dec-10	24-Jan-11																																																	<input type="checkbox"/>	Install LV Power Supply and LV Power Equipment		
A5010	Install Telecon Equipment	20	24-Jan-11	21-Feb-11																																																	<input type="checkbox"/>	Install Telecon Equipment		

CEC02085660_0094

Activity ID	Activity Name	Original Duration	Start	Finish	2008												2009												2010												2011																																																														
					O N D J F M A M J J A S O N O												J F M A M J J A S O N D J												J F M A M J J A S O N D J												J F M A M J J A S O N D J																																																														
A5020	Install Station Control Equipment + AFC Equipment	25	24-Jan-11	28-Feb-11																																																	Install Station Control Equip																																																		
A5030	Package Test Tramstop	5	28-Feb-11	07-Mar-11																																																	Package Test Tramstop																																																		
Trackwork (370m)					509	03-Apr-08	06-Apr-10																																																	06-Apr-10, Trackwork (370m)																																															
1229	CBM - Ducts	13	01-Feb-10	17-Feb-10																																																	CBM - Ducts																																																		
1239	Track laying	8	18-Feb-10	01-Mar-10																																																	Track laying																																																		
1249	Track Finishes	17	02-Mar-10	24-Mar-10																																																	Track Finishes																																																		
1259	Road Crossings	20	02-Mar-10	29-Mar-10																																																	Road Crossings																																																		
12530	Issue Construction Drawings	0		03-Apr-08*																																																	Issue Construction Drawings, 03-Apr-08*																																																		
1259	Fencing	8	25-Mar-10	06-Apr-10																																																	Fencing																																																		
293	OLE Foundations - Drainage	15	11-Jan-10	29-Jan-10																																																	OLE Foundations - Drainage																																																		
650	Bulk Excavation - Subbase	10	02-Dec-09	08-Jan-10																																																	Bulk Excavation - Subbase																																																		
Granton Waterfront (exc.) to Granton Square (Inc.)					744	25-Feb-08	31-Jan-11																																																	31-Jan-11, Granton Waterfront																																															
Granton Square Tram Stop					744	25-Feb-08	31-Jan-11																																																	31-Jan-11, Granton Square																																															
12540	Issue Construction Drawings	0		25-Feb-08*																																																	Issue Construction Drawings, 25-Feb-08*																																																		
175	Civil Engineering and Building Works	65	18-Jan-10	19-Apr-10																																																	Civil Engineering and Building Works																																																		
598	Order REC Supply	0	03-Sep-10																																																		Order REC Supply																																																		
A2860	Deliver and Install Shelter	10	15-Oct-10	29-Oct-10																																																	Deliver and Install Shelter																																																		
A5038	Access for visual inspection for E&M Tram Stop installation (03C Granton Square)	0	29-Sep-10																																																		Access for visual inspection for E&M Tram Stop installation																																																		
A5039	Access for E&M Tram Stop installation (03C Granton Square)	0	29-Oct-10																																																		Access for E&M Tram Stop installation																																																		
A5040	Install LV Power Supply and LV Power Equipment	25	29-Oct-10	06-Dec-10																																																	Install LV Power Supply and LV Power Equipment																																																		
A5050	Install Telecom Equipment	20	06-Dec-10	17-Jan-11																																																	Install Telecom Equipment																																																		
A5080	Install Station Control Equipment + AFC Equipment	25	06-Dec-10	24-Jan-11																																																	Install Station Control Equipment																																																		
A5070	Package Test Tramstop	5	24-Jan-11	31-Jan-11																																																	Package Test Tramstop																																																		
A6240	Installation of SIG-interlocking cubicle	10	12-Nov-10	26-Nov-10																																																	Installation of SIG-interlocking cubicle																																																		
A6250	Commissioning of SIG -interlocking cubicle	5	26-Nov-10	03-Dec-10																																																	Commissioning of SIG -interlocking cubicle																																																		
Granton Road Sub Station					187	14-Dec-09	08-Sep-10																																																	08-Sep-10, Granton Road Sub Station																																															
358	Order REC supply from Scottish Power	0	14-Dec-09																																																		Order REC supply from Scottish Power																																																		
376	Civil Engineering and Building Works	65	18-Jan-10	19-Apr-10																																																	Civil Engineering and Building Works																																																		
A2898	Access for visual inspection for E&M Substation installation (03C Granton Road)	0	19-Mar-10																																																		Access for visual inspection for E&M Substation installation																																																		
A2899	Access for E&M Substation installation (03C Granton Road)	0	20-Apr-10																																																		Access for E&M Substation installation																																																		
A5780	Power Infeed from Public Net available inc HV cable	0	20-Apr-10																																																		Power Infeed from Public Net available inc HV cable																																																		
A5790	Install LV Power Supply and LV Power Equipment	15	20-Apr-10	11-May-10																																																	Install LV Power Supply and LV Power Equipment																																																		
A5800	Installation of TPS Equipment	30	07-Jul-10	19-Aug-10																																																	Installation of TPS Equipment																																																		
A5810	Install Telecom and Scada	15	28-Jul-10	19-Aug-10																																																	Install Telecom and Scada																																																		
A5820	Testing and Commissioning	14	19-Aug-10	08-Sep-10																																																	Testing and Commissioning																																																		
Trackwork (1130m)					521	03-Apr-08	22-Apr-10																																																	22-Apr-10, Trackwork (1130m)																																															
1179	CBM - Ducts	37	09-Oct-09	01-Dec-09																																																	CBM - Ducts																																																		
1189	Track laying	23	02-Dec-09	15-Jan-10																																																	Track laying																																																		
1199	Track Finishes	45	18-Jan-10	19-Mar-10																																																	Track Finishes																																																		
1209	Road Crossings	40	18-Jan-10	12-Mar-10																																																	Road Crossings																																																		
1219	Fencing	23	22-Mar-10	22-Apr-10																																																	Fencing																																																		
12650	Issue Construction Drawings	0		03-Apr-08*																																																	Issue Construction Drawings, 03-Apr-08*																																																		
273	OLE Foundations - Drainage	45	07-Aug-09	08-Oct-09																																																	OLE Foundations - Drainage																																																		
650	Bulk Excavation - Subbase	23	06-Jul-09	06-Aug-09																																																	Bulk Excavation - Subbase																																																		
SECTION 05 ROSEBURN JUNCTION TO GOGAR					741	28-Sep-07	30-Aug-10																																																	30-Aug-10, SECTION 05 ROSEBURN JUNCTION TO GOGAR																																															
Opening Sequence A (Airport to Haymarket)					741	28-Sep-07	30-Aug-10																																																	30-Aug-10, Opening Sequence A (Airport to Haymarket)																																															
05A Roseburn Junction (exc.) to Balgreen Road (Inc.)					741	28-Sep-07	30-Aug-10																																																	30-Aug-10, 05A Roseburn Junction (exc.) to Balgreen Road (Inc.)																																															
E & M Installations					70	21-May-10	30-Aug-10																																																	30-Aug-10, E & M Installations																																															
A4083	Access for visual inspection for E&M wayside installation (05A)	0	21-May-10																																																		Access for visual inspection for E&M wayside installation																																																		
A4084	Access for E&M wayside installation (05A)	0	12-Jun-10																																																		Access for E&M wayside installation																																																		
A4085	Installation of poles and building fixings	18	12-Jun-10	29-Jun-10																																																	Installation of poles and building fixings																																																		
A4090	Overhead Catenary Line	43	30-Jun-10	30-Aug-10																																																	Overhead Catenary Line																																																		
A4098	Access for visual inspection to cable pits for cable laying (05A)	0	22-Jun-10																																																		Access for visual inspection to cable pits for cable laying																																																		
A4099	Access to cable pits for cable laying (05A)	0	14-Jul-10																																																		Access to cable pits for cable laying																																																		

Activity ID	Activity Name	Original Duration	Start	Finish	2008												2009												2010												2011																																						
					O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D	J	F	M	A	M	J	J	A	S	O	N	D
					Gantt chart area with activity bars and milestones																																																																										
243	CBM - Ducts	13	19-Apr-10	05-May-10	Gantt bar from Jun 2009 to Dec 2009																																																																										
530	Tracklaying	20	07-May-10	04-Jun-10	Gantt bar from Jun 2009 to Dec 2009																																																																										
989	Track Finishes	5	07-Jun-10	11-Jun-10	Gantt bar from Jun 2009 to Dec 2009																																																																										
999	Fencing	19	14-Jun-10	08-Jul-10	Gantt bar from Jun 2009 to Dec 2009																																																																										
Balgreen Road Tram Stop		372	30-Jun-08	18-Dec-09	Milestone: 18-Dec-09, Balgreen Road Tram Stop																																																																										
10790	Issue Construction Drawings	0		30-Jun-08*	Milestone: 30-Jun-08*																																																																										
117	Civil Engineering and Builders Work	65	06-Jul-09	05-Oct-09	Gantt bar from Jun 2009 to Dec 2009																																																																										
328	Order REC Supply	0	06-Aug-09		Milestone: Order REC Supply																																																																										
A2300	Deliver and Install Shelter	10	17-Sep-09	01-Oct-09	Gantt bar from Jun 2009 to Dec 2009																																																																										
A5118	Access for visual inspection for E&M Tram Stop installation (05A Balgreen Road)	0	01-Sep-09		Milestone: Access for visual inspection for E&M Tram Stop installation (05A Balgreen Road)																																																																										
A5119	Access for E&M Tram Stop installation (05A Balgreen Road)	0	01-Oct-09		Milestone: Access for E&M Tram Stop installation (05A Balgreen Road)																																																																										
A5120	Install LV Power Supply and LV Power Equipment	25	01-Oct-09	05-Nov-09	Gantt bar from Jun 2009 to Dec 2009																																																																										
A5130	Install Telecom Equipment	20	05-Nov-09	04-Dec-09	Gantt bar from Jun 2009 to Dec 2009																																																																										
A5140	Install Station Control Equipment + AFC Equipment	25	05-Nov-09	11-Dec-09	Gantt bar from Jun 2009 to Dec 2009																																																																										
A5150	Package Test Tramstop	5	11-Dec-09	18-Dec-09	Gantt bar from Jun 2009 to Dec 2009																																																																										
Jenners Depository Sub Station		578	28-Sep-07	11-Jan-10	Milestone: 11-Jan-10, Jenners Depository Sub Station																																																																										
12600	Issue Construction Drawings	0		28-Sep-07*	Milestone: 28-Sep-07*																																																																										
286	Order REC supply from Scottish Power	0	15-Jun-09		Milestone: Order REC supply from Scottish Power																																																																										
296	Civil Engineering and Building Works	65	06-Jul-09	05-Oct-09	Gantt bar from Jun 2009 to Dec 2009																																																																										
A2278	Access for visual inspection for E&M Substation installation (05A Jenners Depositor	0	04-Sep-09		Milestone: Access for visual inspection for E&M Substation installation (05A Jenners Depo																																																																										
A2279	Access for E&M Substation installation (05A Jenners Depository)	0	06-Oct-09		Milestone: Access for E&M Substation installation (05A Jenners Depository)																																																																										
A5830	Power Infeed from Public Net available inc HV cable	0	06-Oct-09		Milestone: Power Infeed from Public Net available inc HV cable																																																																										
A5840	Install LV Power Supply and LV Power Equipment	15	06-Oct-09	26-Oct-09	Gantt bar from Jun 2009 to Dec 2009																																																																										
A5850	Installation of TPS Equipment	30	27-Oct-09	08-Dec-09	Gantt bar from Jun 2009 to Dec 2009																																																																										
A5860	Install Telecom and Scada	15	17-Nov-09	08-Dec-09	Gantt bar from Jun 2009 to Dec 2009																																																																										
A5870	Testing and Commissioning	14	09-Dec-09	11-Jan-10	Gantt bar from Jun 2009 to Dec 2009																																																																										
05B Balgreen Road (exc.) to Edinburgh Park (inc.)		483	05-Feb-08	01-Dec-09	Milestone: 01-Dec-09, 05B Balgreen Road (exc.) to Edinburgh Park (inc.)																																																																										
E & M Installations		104	02-Jun-09	27-Oct-09	Milestone: 27-Oct-09, E & M Installations																																																																										
A4123	Access for visual inspection for E&M wayside installation (05B)	0	02-Jun-09		Milestone: Access for visual inspection for E&M wayside installation (05B)																																																																										
A4124	Access for E&M wayside installation (05B)	0	24-Jun-09		Milestone: Access for E&M wayside installation (05B)																																																																										
A4125	Installation of poles and building fixings	36	24-Jun-09	29-Jul-09	Gantt bar from Jun 2009 to Dec 2009																																																																										
A4130	Overhead Catenary Line	87	30-Jul-09	24-Oct-09	Gantt bar from Jun 2009 to Dec 2009																																																																										
A4138	Access for visual inspection to cable pits for cable laying (05B)	0	18-Jul-09		Milestone: Access for visual inspection to cable pits for cable laying (05B)																																																																										
A4139	Access to cable pits for cable laying (05B)	0	09-Aug-09		Milestone: Access to cable pits for cable laying (05B)																																																																										
A4140	Install Electrical Cables	40	09-Aug-09	17-Sep-09	Gantt bar from Jun 2009 to Dec 2009																																																																										
A4150	Install Fibre Optic Cables	40	09-Aug-09	17-Sep-09	Gantt bar from Jun 2009 to Dec 2009																																																																										
A4160	Install Signaling Wayside Equipment	40	18-Sep-09	27-Oct-09	Gantt bar from Jun 2009 to Dec 2009																																																																										
Balgreen Road (exc.) to Saughton Road North (inc.)		463	05-Feb-08	01-Dec-09	Milestone: 01-Dec-09, Balgreen Road (exc.) to Saughton Road North (inc.)																																																																										
Carricknowe Bridge (S23)		206	16-Jul-08	11-May-09	Milestone: 11-May-09, Carricknowe Bridge (S23)																																																																										
10810	Issue Construction Drawings	0		16-Jul-08*	Milestone: 16-Jul-08*																																																																										
Garrick Knowe disruptive possessions		187	15-Aug-08	11-May-09	Milestone: 11-May-09, Garrick Knowe disruptive possessions																																																																										
Establishment		186	15-Aug-08	09-May-09	Milestone: 09-May-09, Establishment																																																																										
12	Temporary Fencing	5	15-Aug-08	21-Aug-08	Gantt bar from Jun 2009 to Dec 2009																																																																										
13	Haul Roads	5	15-Aug-08	21-Aug-08	Gantt bar from Jun 2009 to Dec 2009																																																																										
24	Possessions 1 (12hrs)	0	22-Aug-08		Milestone: Possessions 1 (12hrs)																																																																										
A15	Possessions 2 (12hrs)	0	25-Aug-08		Milestone: Possessions 2 (12hrs)																																																																										
B14	Erect Network Rail Safety Barrier	2	22-Aug-08	25-Aug-08	Gantt bar from Jun 2009 to Dec 2009																																																																										
C13	Possessions 4 (12hrs)	0		09-May-09	Milestone: Possessions 4 (12hrs), 09-May-09																																																																										
C14	Remove Crash Deck and Barriers	1	07-May-09	07-May-09	Gantt bar from Jun 2009 to Dec 2009																																																																										
North Abutment		122	22-Aug-08	16-Feb-09	Milestone: 16-Feb-09, North Abutment																																																																										
Excavate and Blind		9	22-Aug-08	04-Sep-08	Milestone: 04-Sep-08, Excavate and Blind																																																																										
105	Excavate	4	29-Aug-08	03-Sep-08	Gantt bar from Jun 2009 to Dec 2009																																																																										
16	Blinding	1	04-Sep-08	04-Sep-08	Gantt bar from Jun 2009 to Dec 2009																																																																										
96	Temporary Support to Railway Lines	5	22-Aug-08	28-Aug-08	Gantt bar from Jun 2009 to Dec 2009																																																																										
Base Construction		9	05-Sep-08	17-Sep-08	Milestone: 17-Sep-08, Base Construction																																																																										

